



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-057-10017-0000

RECEIVED
STATE CORPORATION COMMISSION

SEP 21 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Knight of Time Petroleum Co. has this

date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Time Petroleum Co.

Complete Address: 815 Union National Bldg. Wichita, Kansas

Lease Name: Cook Well No. # 1

Location: C W/2 SE Sec. 36 Twp. 28 Rge. 22 (E/W)

County Ford Total Depth 5244' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Knight was instructed to plug the well as follows:

8 5/8"-282' Circulated w/cement. 4 1/2"-5243' Cemented.

Top Perforations 5180' Plug bottom w/sand and 5 Sax.cement top

Mud 4950' to 600' Cement at 4950' Spotted 25 Sax.cement 600' to 525'

Mud 525' to 282' Spotted 25 Sax.cement 282' to 207'

Mud 207' to 40' Plug 10 Sax.cement 40' to 0

Very truly yours,

Conservation Division Agent