



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

20 October 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)
15-057-20,235-0000

Dear Sir:

Mr. Pat Smith of Big A. Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Sam Garry Oil Producer

Complete Address: 4 Inverness Court East Englewood Colo. 80112

Lease Name: Keller Well No. 23-14

Location: C-SE-SW Sec. 23 Twp. 28 S Rge. 23 W (E) (W)

County: Ford Total Depth: 5874'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Smith was instructed to plug the well as follows:

There is 554' of 8 1/2" surface casing cement circulated. The Dakota was topped at 740' to 900'. 1st plug at 925' with 70 sks of cement after circulating for 10 min. 2nd plug pushed rubber plug to 525' then pumped 35 sks of cement on top of rubber plug. 3rd plug 40' to 0' on solid bridge with 10 sks cement. Put 5 sks of cement in rat hole & 5 sks of cement in mouse hole. The farmer wants the water well and was advised to record it with the Corp. Com.
Very truly yours,
Plugging accomplished by Halliburton Co. out of Liberal Kansas

Paul L. Smith
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

OCT 22 1981
10-22-1981
CONSERVATION DIVISION
Wichita, Kansas