



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

5 November 1981

RECEIVED  
STATE CORPORATION COMMISSION

NOV 10 1981

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

15-097-29834-0000

Dear Sir:

Mr. Vaughn Thompson of Stearling Drilling Co. was this 11-10-1981 date requested permission to plug the following described well:

Operator's Full Name: Berney Oil Co. Super. Dir. Barrion Oil Co.

Complete Address: 970-4th Financial Center Wichita Kansas 67202

Lease Name: Mull Well No. 1

Location: C-SW 1/4 to 275-16th Sec. 6 Twp. 27S Rge. 16W (E) (W)

County: Rowa Total Depth: 4800'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Thompson was instructed to plug the well as follows:

The anhydrite was topped at 1057'. There is 450' of 8 5/8" surface casing  
Cement circulated. 1st plug 1050' with 50 Sbk. cement. 2nd plug pushed  
rubber plug to 430' with 40 Sbk. of cement pumped on top of it. 3rd plug 40' to 0'  
with 10 Sbk. of cement. Then pumped 5 Sbk. each in rat hole, mouse  
hole & 5 Sbk. of cement in water well. Plugging accomplished  
by Halliburton Co. out of Pratt Kans.

Very truly yours,

Paul Luthi  
Conservation Division Agent