

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

NOV 12 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

CONSERVATION DIVISION
 Wichita, Kansas

11-12-1963

Dear Sir:

Mr. Jess Bailey of Bachus Oil Co. has this
 date requested permission to plug the following described well:

Mr. Bailey guarantees payment of the plugging fee.

Operator's full Name: Bachus Oil Co.

Complete Address: 721 E. Central, Wichita, Kansas

Lease Name: Meade Well No. # 1

Location: NW SW Sec. 36 Twp. 27 Rge. 7 (E) (W) W

County Kingman Total Depth 4308 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bailey was instructed to plug the well as follows:

214' of 8 5/8" surface pipe, cemented with 200 sacks.

Fill hole with drilling mud to 200', 1st cementing plug,

1/2 sack hulls, cement with 25 sacks. Fill hole with drill-

mud to 40', 2nd cementing plug, 1/2 sacks hulls, cement with

10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Achie Elving
 Conservation Division Agent