

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSIONMAR 21 1966
CONSERVATION DIVISION
Wichita, Kansas

3-21-1966

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Web Hill of Mack Oil Company has this
date requested permission to plug the following described well:

Mr. Hill guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company

Complete Address: 812 Union Center Bldg., Wichita, Kansas

Lease Name: McKenna Well No. # 2

Location: C SW NE Sec. 35 Twp. 27 Rge. 7 (E) (W) W

County Kingman Total Depth 3640' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hill was instructed to plug the well as follows:

255' of 10 3/4" surface pipe, cement circulated with 250 sacks.
Fill hole with drilling mud to 250', 1st cementing plug, bridge.
with hulls, and cement with 30 sacks. Fill hole with drilling mud
to 40', 2nd cementing plug, bridge with hulls, and cement with 15
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving