

RECEIVED

SEP 06 2002

KCC WICHITA

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 1508110003-0001 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date. 8/03

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549
(owner/company name) (operator's)
ADDRESS 701 S. TAYLOR, STE 400 CITY AMARILLO
STATE TEXAS ZIP CODE 79101 CONTACT PHONE (806) 457-4600
LEASE GREGG EM WELL# 4 SEC. 32 T. 28 R. 34 (xxxx/West)

- C - SE - SW SPOT LOCATION/QQQQ COUNTY HASKELL
660 FEET (in exact footage) FROM S/X (circle one) LINE OF SECTION (NOT Lease Line)
3000 FEET (in exact footage) FROM E/X (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____
CONDUCTOR CASING SIZE NONE SET AT _____ CEMENTED WITH _____ SACKS
SURFACE CASING SIZE 8 5/8 SET AT 1853 CEMENTED WITH 750 SACKS
PRODUCTION CASING SIZE 5 1/2 SET AT 5501 CEMENTED WITH 325 SACKS
LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: CIBP:5200,5419. PERFS: 5433-5472, 4664-4670, 4537-4567, 4472-4484, 4061-4071, 4110-4120

ELEVATION 2997 / _____ T.D. 5502 PBSD 5200 ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING SET CIBP @ 4000. DUMP 2 SXS CMT. SHOOT OFF 5 1/2 100' ABOVE FREE POINT. SPOT 50 SXS CMT AT 2800-2620. DISPLACE WITH 9PPG MUD. TAG. SPOT 50 SXS CMT AT 1870-1720. DISPLACE WITH MUD. TAG. SPOT 30 SXS CMT FROM 690-600. DISPLACE WITH MUD. TAG. SPOT 10 SXS CMT FROM 40 TO SURFACE. CUT OFF AND CAP 8 5/8 3' BELOW GL.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES
If not explain why? LOGS SUBMITTED W/ ORIG. COMPLETION REPORT OR DRILLER'S LOG.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
DAWN NEASE PHONE# (620) 544-4344
ADDRESS PO BOX 40 City/State HUGOTON, KS

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151
(company name) (contractor's)
ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT
DATE: 9/3/2002 AUTHORIZED OPERATOR/AGENT: Craig R. Walters
CRAIG R. WALTERS, P.E. (Signature)
DIVISION PRODUCTION ENGINEER

8/03

1/03



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Anadarko Petroleum Corporation
1201 Lake Robbins Drive
The Woodlands, TX 77380

September 10, 2002

Re: E M GREGG #4
API 15-081-10003-00-01
CSESW 32-28S-34W, 660 FSL 3000 FEL
HASKELL COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(316) 225-8888