

RECEIVED  
11-5-02  
NOV 05 2002

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

KCC WICHITA

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-081-10212-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549  
(owner/company name) (operator's)  
ADDRESS 701 S. TAYLOR, SUITE 400 CITY AMARILLO  
STATE TEXAS ZIP CODE 79101 CONTACT PHONE (806) 457-4600  
LEASE McCOY WELL# 2-32 SEC. 32 T. 28 R. 34 (xxxx/West)

- C - SE - SE SPOT LOCATION/QQQQ COUNTY HASKELL  
660 FEET (in exact footage) FROM S/X (circle one) LINE OF SECTION (NOT Lease Line)  
660 FEET (in exact footage) FROM E/X (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET#                     

CONDUCTOR CASING SIZE                      SET AT                      CEMENTED WITH                      SACKS

SURFACE CASING SIZE 8-5/8" SET AT 1846 CEMENTED WITH 750 SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 5491 CEMENTED WITH 300 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: PERF: 4686-4710, 5430-5466. PKR @ 5380.

ELEVATION 2997 / 3005 T.D. 5503 PBD 5502 ANHYDRITE DEPTH NA  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING BAKER MODEL D PKR @ 5380. ETOF @ 3093 (2-1/16" TBG & RODS).  
DUMP 35 SXS CMT. DISPLACE WITH 9 PPG MUD TO TOP OF FISH. SHOOT OFF 5-1/2" CSG @ +/-  
1870. SPOT 50 SXS FROM 1870 TO 1720. SPOT 25 SXS FROM 690 TO 615. SPOT 10 SXS FROM 40  
TO 4. CUT OFF AND CAP 8-5/8" CSG 4 BELOW GL. RESTORE LOCATION.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? LOGS SUBMITTED W/ ORIG. COMPLETION REPORT OR DRILLER'S LOG.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

DAWN NEASE PHONE# (620) 544-4344

ADDRESS PO BOX 40 City/State HUGOTON, KS 67951

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151  
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?)                     

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 11/1/2002 AUTHORIZED OPERATOR/AGENT: Craig R. Walters

CRAIG R. WALTERS, P.E. (Signature)  
DIVISION PRODUCTION ENGINEER



## *Kansas Corporation Commission*

*Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner*

### **NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Anadarko Petroleum Corporation  
1201 Lake Robbins Drive  
The Woodlands, TX 77380

November 05, 2002

Re: McCOY Unit #2-32  
API 15-081-10212-00-00  
CSESE 32-28S-34W, 660 FSL 660 FEL  
HASKELL COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams  
Production Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(316) 225-8888