

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-081-75003 ⁰⁶¹⁷⁰⁻⁰⁰⁰⁰ (of this well) 6/87
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Amoco Production Company OPERATORS LICENSE NO. 5952

ADDRESS P. O. Box 432 Liberal, KS 67901 PHONE # (316) 624-6241

LEASE (FARM) K. H. Reimer "B" WELL NO. 1 WELL LOCATION SE NW COUNTY Haskell

SEC. 34 TWP. 28S RGE. 34 or (W) TOTAL DEPTH 5600 PLUG BACK TD 5551

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8 SET AT 752 CEMENTED WITH 750 SACKS

CASING SIZE 5-1/2 SET AT 5594 CEMENTED WITH 250 SACKS

PERFORATED AT 5293-98 5436-42

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL See back of form

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN November 26, 1986

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Bob Heath PHONE # (316) 624-6241

ADDRESS P. O. Box 432 Liberal, KS 67901

PLUGGING CONTRACTOR To be bid LICENSE NO. NOV 4 1983 ¹¹⁻⁴⁻⁸⁶

ADDRESS _____ PHONE # () _____

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Larry L. Smith
(Operator or Agent)

DATE: 11-3-86

①



Amoco Production Company

P. O. Box 432
Liberal, KS 67901

15-081-00170-0000

October 30, 1986

File: RAR-729-400.1

Plugging and Abandonment Procedure
K. H. Reimer "B" No. 1
Section 34-28S-34W
Haskell County, Kansas

Detailed below is the recommended plugging and abandonment procedure for the subject well. Depths are relative to the Induction-Electrical log run by Schlumberger on December 11, 1964. Note that this procedure is for KCC permitting purposes only.

1. MIRUSU or casing pullers, and pull 2 7/8" tubing, pump, and rods.
2. Run a gauge ring and CIBP, set CIBP at 5200', cap with 2 sacks cement.

NOTE: Well has a casing leak, suspected to be in the Glorietta. Casing may be tight, therefore, if it becomes impossible to set plug as specified, contact Liberal for instructions.

3. Locate free point of 5 1/2" casing (see attached wellbore sketch), cut off and pull casing. Cement top is unknown.
4. Spot a 50 sack 50-50 Poz cement plug across the 5 1/2" casing stub.
5. Spot a 75 sack cement plug across the 8 5/8" surface casing shoe (50' in and out of casing shoe), shoe set at 752'.
6. Spot a 50 sack cement plug from 40-5'.
7. Dig out cellar, cut off surface casing at 5'. Weld on steel cap with well and location I.D.
8. Restore location.

NOTE: All intervals between cement plugs must contain mud of at least 9.0 ppg density, and 36 quart-second API viscosity. A representative of the KCC must be notified at least five days prior to the actual plugging operation to discuss plugging methods. They (KCC) can be contacted at (316) 225-6760.

A wellbore sketch is attached for your reference.

C. H. Kelm

BSP/bka

Attachment

P&A/BSP

NOV 4 1986

State of Kansas



JOHN CARLIN
MICHAEL LENNEN
MARGALEE WRIGHT
KEITH R. HENLEY
JUDITH A. McCONNELL
BRIAN J. MOLINE

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1288

Extension
~~THIS NOTICE~~ THIS NOTICE
MAY 4 '87 FEB 4 '87
EXPIRES EXPIRES
90 Days

November 4, 1986

WELL PLUGGING NOTICE
15-081-00170-0000

K. H. Reimer "B" #1
SE NW
Sec. 34-28S-34W
Haskell County

Amoco Production Company
P. O. Box 432
Liberal, KS 67901

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

Jack McCord, Director

Please contact the district office to review your suggested method of plugging
DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760
five days prior to plugging the well (KAR-82-3-113).