

15-151-10036-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER completed 10-29-85 (of this well) 6/86
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Cities Service Oil & Gas Corporation OPERATORS LICENSE NO. 5447

ADDRESS 3545 NW 58th Street, Oklahoma City, OK 73112 PHONE # (405) 949-4400

LEASE (FARM) Harrel D WELL NO. 1 WELL LOCATION 990' ESL, COUNTY Pratt

SEC. 34 TWP. 29S RGE. 13 ~~XX~~ (E) or (W) TOTAL DEPTH 4619' 330' FWL PLUG BACK TD 4617'

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 406' CEMENTED WITH 300 SACKS

CASING SIZE 5-1/2" SET AT 4596' CEMENTED WITH 200 SACKS

PERFORATED AT 4596' to 4619' open hole

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Fill with sand to 4546'. Dump 5 sx cement

on top of sand. Run free point and shoot off 5-1/2" casing. Pull 5-1/2" casing. Pump

down 8-5/8" as follows: 35 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, 8-5/8"
with pu plug, 125 (If additional space is needed use back of form) sx cement.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? completed on 10-29-85
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN December 26, 1985

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Earl Rollings PHONE # (316) 672-9388

ADDRESS Box 381; Pratt, Kansas 67124

PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NO. 6050

ADDRESS El Dorado, Kansas Box 347, Chase, KS 67524 PHONE # (316) 938-2457

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Raymond Hui *Raymond Hui*
(Operator or Agent)

① 12-23-85 DEC 23 1985 DATE: 12-20-85

State of Kansas



JOHN CARLIN
MICHAEL LENNEN
MARGALEE WRIGHT
KEITH R. HENLEY
JUDITH A. McCONNELL
BRIAN J. MCLINE

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

MAR 23 1986

EXPIRES

December 23, 1985
WELL PLUGGING NOTICE

Harrel D #1
990'FSL 330'FWL
Sec. 34-29S-13W
Pratt County

Cities Service Oil & Gas Corporation
3545 NW 58th Street
Oklahoma City, OK 73112

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

Handwritten signature of William R. Bryson in cursive script.

William R. Bryson, Director

Please submit your proposal for plugging the above captioned well to
DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760
five days prior to plugging the well (KAR-82-3-113).