

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
AUG 4 1971
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Cameron of H-30 Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Cameron guarantees payment of the plugging fee.Operator's full Name: Crest Petrolaum Inc.Complete Address: 6631 E. Kellogg Wichita, KsLease Name: Stoehr Well No. 1Location: C NW/SW Sec. 31 Twp 27s Rge. 5 (E)(W) WCounty: Kingman Total Depth 3792 Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Cameron was instructed to plug the well as follows:209 ft 8 5/8 surface pipe cemented with 175 sacks. Fillhole to 190 ft, plug, 1/2 sack hulls, 35 sacks cement. Mudto 40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface.2 sacks cement in rat hole.

Very truly yours,

Conservation Division Agent