

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 7 1966
10-07-66

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Sioux Petroleum

Complete Address: 104 East Kansas, Medicine Lodge, Kansas

Lease Name Keys Well No. # 1

Location NE NE NE Sec. 35 Twp. 29 Rge. 13 (E) (W) W

County Pratt Total Depth 4607'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Clarke Corporation, Inc.

Address: Chapin Bldg., Medicine Lodge, Kansas License No. 583

Operation Completed: Hour 11:45AM Day 5th Month Oct. Year 1966

The Above well was plugged as follows:

821' of 8 5/8" surface pipe, cement circulated. 4589' of 5 1/2" long string,
cemented with 125 sacks. Plug back T.D. 4559'. Top perferation 4443'.
Bottom of the hole was sanded to 4400', and cemented with 5 sacks, through
the dump bailer. 3160' of 5 1/2" long string was recovered from the hole.
Fluid level in the hole was at 410', bridge plug and rock bridge from
410' to 400', and cemented with 25 sacks. Hole was filled with mud to
40', rock bridge from 40' to 30', and cemented with 10 sacks to the
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Cheung
Well Plugging Supervisor

DATE 10/7/66
INV. NO. 4065-u