

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasWell Plugging Authority,
issued March 27, 1967.Operator's Full Name Santa Fe Pipe & Supply, Inc.Complete Address: P. O. Box 562, Great Bend, KansasLease Name Larrison "A" Well No. # 2Location NW NE NW Sec. 35 Twp. 29 Rge. 13 (E) (W) WCounty Pratt Total Depth 4600'Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Santa Fe Pipe & Supply, Inc.Address: P. O. Box 562, Great Bend, Kansas License No. 574Operation Completed: Hour 5:30PM Day 31st Month March Year 1967

The Above well was plugged as follows:

857' of 8 5/8" surface pipe, cement circulated. 4599' of 5 1/2" long string,
cemented with 150 sacks. Plug back T.D. 4571'. Top perforation 4553'.
Bottom of the hole was sanded to 4525', and cemented with 5 sacks, through
the dump bailer. 4143' of 5 1/2" long string was recovered from the hole.
Hole was filled with mud to 400', rock bridge from 400' to 385', and
cemented with 25 sacks, Hole was filled with mud to 40', rock bridge
from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

4/3/67

INV. NO.

4988-11

Signed:

Arlis Elving
Well Plugging Supervisor