

15-151-36088-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC - 6 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Sioux Petroleum

Complete Address: Medicine Lodge, Kansas

Lease Name Keys Well No. # 1

Location SW SW NE Sec. 35 Twp. 29 Rge. 13 (E) (W) W

County Pratt Total Depth 4611'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling, Inc

Address: 815 Wichita, Plaza, Wichita, Kansas License No.

Operation Completed: Hour 6:30 PM Day 4th Month Dec. Year 1965

The Above well was plugged as follows:

200' of 10 3/4" surface pipe, cement circulated with 175 sacks, Fluid
level in the hole was at 90'. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 200', and cemented with 30 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with dry cement and hulls on fluid at 40', and
cemented with 15 sacks, to the base of the cellar. Rat hole bridged
and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 12/9/65
INV. NO. 2352-W