

Form CP-3  
Rev. 6-26-62

*14*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
APR 29 1965  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Great Bend Pipe & Supply Co., Inc.  
Complete Address: Drawer "B", Great Bend, Kansas  
Lease Name Larrison-Blaine Well No. # 1  
Location NE SW SE Sec. 34 Twp. 29 Rge. 13 (E) (W) W  
County Pratt Total Depth 4610'  
Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated:         
Plugging Contractor: Knight Casing Pulling Company  
Address: Box 405, Chase, Kansas License No. 436  
Operation Completed: Hour 11:30AM Day 28th Month April Year 1965

The Above well was plugged as follows:

886' of 8 5/8" surface pipe, cement circulated. 4604' of 4 1/2" long string,  
cemented with 180 sacks. Plug back to 4438'. Top perforation 4396'. Bot-  
tom of the hole was sanded to 4360', and cemented with 3 sacks. 3798' of  
4 1/2" long string was recovered from the hole. Hole was filled with mud  
to 275', and 10' of rock bridge, and cemented with 25 sacks. Hole was  
filled with mud to 40', and 10' of rock bridge, and cemented with 10  
sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 4/29/65  
INV. NO. 1069-W

Signed: Archie Elving  
Well Plugging Supervisor