

10  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

NOV 15 1965

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Colorado Oil Company

Complete Address: 915 Union National Bldg., Wichita, Kansas

Lease Name Lee Well No. # 1

Location NE  
C NE NW Sec. 33 Twp. 29 Rge. 13 (E) (W) W

County Pratt Total Depth 4735'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 12:15PM Day 13th Month Nov. Year 1965

The Above well was plugged as follows:

955' of 8 5/8" surface pipe, cemented with 450 sacks. 4602' of 4 1/2" long  
string, cemented with 150 sacks. Plug back to 4564'. Top perferation  
4495'. 10 sacks of cement and plug was punped on bottom to 4350'  
3800' of 4 1/2" long string was recovered from the hole. Hole was filled  
with mud to 300', rock bridge from 300' to 290', and cemented with 25  
sacks. Hole was filled with mud to 40', rock bridge from 40' to 30',  
and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving  
Well Plugging Supervisor

INVOICED

DATE 11/15/65  
INV. NO. 2196-W