

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name F.G. Holl

Complete Address 6427-E. Kellogg, Wichita, Ks. 67207

Lease Name Wright Well No. 1

Location SE SE NW Sec. 33 Twp. 29S Rge. 13 (E) (W) X

County Pratt Total Depth 4740

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176-Chase, Ks. 67524 License No. 683

Operation Completed: Hour 11:30 Am. Day 24 Month 8 Year 1979

The above well was plugged as follows:

262' 8 5/8" casing w/300 sax cement. 5 1/2" casing set at 4718' w/125
sax cement. Plug back to 4440'-Preforated at 4401'-4405'-4418'-4422'-
Sand back to 4375'-Top sand w/5 sax mixed cement w/ dump bailer. Pull
3415' 5 1/2' casing. Sun mixed & pumped 8 sax hulls-25 sax gel, release
plug-mixed & pumped 125 sax 50/50 Posmix cement w/4% gel & 3% cc to
top of casing. Shut in w/200# pressure.

RECEIVED
STATE CORPORATION COMMISSION

AUG 27 1979

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 8-31-79

INV. NO. 0297-W