

4

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 7 - 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Well Plugging Authority,  
issued February 2, 1968.

Operator's Full Name Apco Oil Corporation  
Complete Address: 1000 Liberty Bank Bldg., Oklahoma City, Oklahoma 73102  
Lease Name Jem Well No. # 1  
Location NW NW SE Sec. 28 Twp. 29 Rge. 13 (E) (W) W  
County Pratt Total Depth 4592'  
Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_  
Other well as hereafter indicated: \_\_\_\_\_  
Plugging Contractor: Santa Fe Pipe & Supply, Inc.  
Address: Box 562, Great Bend, Kansas 67530 License No. 574  
Operation Completed: Hour 11:00AM Day 4th Month March Year 1968

The Above well was plugged as follows:

353' of 8 5/8" surface pipe, cement circulated. 4591' of 4 1/2" long string,  
cemented with 40 sacks. This is an open hole. Bottom of the hole was sanded  
to 4500', and cemented with 4 sacks, through the dump bailer, with cement  
from 4500' to 4450'. 3025' of 4 1/2" long string was recovered from the hole.  
Fluid in the hole was bailed down to 200', bridge plug and rock bridge from  
from 200' to 190', and cemented with 25 sacks, with cement from 190' to 115'.  
Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented  
with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 3/7/68  
INV. NO. 7379-W