

KANSAS

FORM CP-3
Rev. 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-057-20,176-0000

245 North Water
Wichita, KS 67202

Operator's Full Name IMPERIAL OIL COMPANY

Complete Address 720 4TH FINANCIAL CENTER - WICHITA, MO 67202

Lease Name COOK Well No. F 1-36

Location C-NW-NE Sec. 36 Twp. 28 Rge. 22 (East) (West)

County FORD Total Depth 5372 FL

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor SUN CEMENTING CO.

Address BOX 169 GREAT BEND, MO License No. _____

Operation Completed: Hour 1:00 ^{PM} Day 15 Month DEC Year 1980

RECEIVED
CONSERVATION DIVISION
Wichita, Kansas
DEC 17 1980
STATE CORPORATION COMMISSION

The above well was plugged as follows:

8 5/8" 675^{FL} SP. CUM. w/ 250^{SE} → 4 1/2" SET @ 5371^{FL} w/ 200^{SE} CNT.
PLUG. BACK. 5300^{FL} → PERFS - 5126^{FL} - 5130^{FL}
SHOT PIPE 6 TIMES - RECOVERED 3680^{FL}
PUMPED BOTTOM - PUT IN 1^{HULL} → 35^{SE} COMMON CNT. → PUMP PLUG. to 4800^{FL}
PUMPED IN WITH PUMP. TRUCK.
ORDERED 140^{SE} 50/50 PREMIX 6% GEL. 21^{SE} GEL. → 4^{SE} HULL'S + 8 5/8" PLUG.
PUT IN 4^{SE} HULL'S → 12^{SE} GEL → 40^{SE} CNT. → 9^{SE} GEL. → RELEASED PLUG.
FIND 40^{SE} CNT. - MAX. PRESSURE, 500^{LB} SHUT IN PRESSURE 100^{LB}.
CEMENTED BY SUN CNT.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 1-12-81
INV. NO. 3864-W

Signed: Imperial [Signature]
Conservation Division Agent