

15-057-10017-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 21 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Time Petroleum Co.

Complete Address: 815 Union Natl. Bldg. Wichita, Kansas

Lease Name Cook Well No. # 1

Location C W/2 SE Sec. 36 Twp. 28 Rge. 22 (E) (W)

County Ford Total Depth 5244'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Chase, Kansas License No. 436

Operation Completed: Hour 4 PM Day 19 Month 9 Year 65

The Above well was plugged as follows:

8 5/8"-282' Circulated w/cement. 4 1/2"-5243' Cemented. Top perforations 5180'

Plug bottom w/sand and 5 Sax. cement top cement at 4950' Mud 4950' to 600'

Spotted 25 Sax. cement 600' to 525' Mud 525' to 282'

Spotted 25 Sax. cement 282' to 207' Mud 207' to 40'

Plug, 10 Sax. cement 40' to 0 Pulled 3131' 4 1/2" pipe. Company Pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 9/21/65
INV. NO. 1843-W

Signed: [Signature]
Well Plugging Supervisor