

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-05-7-20,235-0000 ✓ K

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name Sam Gary Oil Producer

Complete Address #4 Inverness Court East Englewood Colo 80112

Lease Name Keller Well No. 23-14

Location C-SE-SW Sec. 23 Twp 28S Rge 23W (East) (West)

County Jord Total Depth 5874'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Big A. Drilling Co.

Address 1717-17th St. Suite 2860 Denver Colo License No. \_\_\_\_\_

Operation Completed: Hour: 10:15 PM Day: 20 Month: October Year: 19 81

Plugging Operations attended by Agent? All  Part  None

The above well was plugged as follows:

There is 554' of 8 5/8" surface casing cement circulated. The Dakota was topped at 740' to 900'. 1st plug at 925' with 70 skb of cement after circulated for 10 min. 2nd plug pushed rubber plug to 525' then pumped 35 lbs. of cement on top of rubber plug. 3rd plug 40' to 0' on solid bridge with 10 skb of cement. Put 5 skb of cement in rat hole + 5 skb in mouse hole. The farmer wants the water well and they were advised to record it with Corp. Comm.

Plugging accomplished by Halliburton Co. out of Liberal, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

OCT 23 1981

I hereby certify that the above well was plugged as herein stated.

DATE 11-19-81

Signed: Paul [Signature]  
Conservation Division Agent

10-22-81  
CONSERVATION DIVISION  
Wichita, Kansas

INV. NO. 8346-W

190:91