


9

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

SEDGWICK County. Sec. 26 Twp. 27S Rge. (E) 3 (W)
Location as "NE/CNW/SW" or footage from lines. C NE NW
Lease Owner AYLWARD DRILLING COMPANY
Lease Name WELLS Well No. 1
Office Address 909 FIRST NATL. BANK BLDG., WICHITA, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed JULY 24, 19 66
Application for plugging filed PHONE 7/24/66 JULY 26, 19 66
Application for plugging approved JULY 24, 19 66
Plugging commenced JULY 24, 19 66
Plugging completed JULY 24, 19 66
Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well PAUL TURPIN
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4219 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	250	8-5/8"	250'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO 210 FEET. SET FIRST PLUG WITH 1/2 SACK HULLS AND 20 SACKS CEMENT. FILLED HOLE WITH HEAVY MUD TO 40 FEET. SET SECOND PLUG WITH 1/4 SACK HULLS AND 10 SACKS CEMENT. MUDDED RAT HOLE TO 10 FEET OF SURFACE AND PLUGGED WITH 2 SACKS CEMENT.

RECEIVED
STATE CORPORATION COMMISSION
JUL 28 1968
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GABBERT-JONES, INC.
Address 514 ORPHEUM BLDG., WICHITA, KANSAS 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
F. F. HALL (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *F. F. Hall*
514 ORPHEUM BLDG., WICHITA, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 26 day of JULY, 19 66

My commission expires FEBRUARY 1, 1968
Barbara J. Layton
BARBARA J. LAYTON Notary Public.

9

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

WELLS #1 26-27S-3W
C NE NW SECTION 19-28S-1W
SEDGWICK COUNTY, KANSAS

COMMENCED: JULY 13, 1966
COMPLETED: JULY 24, 1966

OPERATOR - AYLWARD DRILLING COMPANY

DEPTH		FORMATION	REMARKS
FROM	TO		
0	70	CLAY AND GRAVEL	
70	249	SAND AND SHALE	
249	250	LIME	RAN 11 JOINTS OF 8-5/8" CASING, SET @ 250' w/225 SACKS CEMENT.
250	411	LIME	
411	1103	SHALE AND LIME	
1103	1265	LIME	
1265	3126	LIME AND SHALE	
3126	3334	LIME	
3334	3730	LIME AND SHALE	
3730	4097	LIME	
4097	4111	SHALE	
4111	4205	SHALE AND SAND	
4205	4219	SHALE	
4219	TD		DRY AND ABANDONED.

RECEIVED
STATE CORPORATION COMMISSION
AUG 28 1966
CONSERVATION DIVISION
WICHITA, KANSAS

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C NE NW SECTION 19-28S-1W, SEDGWICK COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall

E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 26TH DAY OF JULY, 1966, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
BARBARA J. LAYTON, NOTARY PUBLIC

My Commission Expires February 1, 1968.