


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Pratt County, Sec. 35 Twp. 29 Rge. 13W (EX) (W)
Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner Sioux Petroleum
Lease Name Keys Well No. 1
Office Address 104 East Kansas Medicine Lodge, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____ 19____
Application for plugging filed September 19 66
Application for plugging approved September 19 66
Plugging commenced October 5th 19 66
Plugging completed October 5th 19 66
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4607 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	821	None
				5 1/2"	4589'	3160'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

821' of 8 5/8" surface pipe, cement circulated, 4589' of 5 1/2" long string, cemented with 125 sacks. Plug back T.D. 4559'. Top perforation 4443'. Bottom of the hole was sanded to 4400', and cemented with 5 sacks cement through dump bailer. 3160' of 5 1/2" long string was recovered from the hole. Fluid level in the hole was at 410'. bridge plug and rock bridge from 410' to 400' and cemented with 25 sacks. Hole was filled with mud to 40' rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

RCWD
10-07-66

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation, Inc.
Address Chapin Bldg., Medicine Lodge, Kansas

STATE OF _____, COUNTY OF _____, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____

(Address) _____

SUBSCRIBED AND SWORN TO before me this _____ day of _____, 19____

My commission expires _____

Notary Public.