

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15151-01747-60-00

LEASE NAME Irene

WELL NUMBER 1-35

SPOT LOCATION NE-SW-NW

SEC. 35 TWP. 29 RGE. 13 XX or (E)

COUNTY Pratt

Date Well Completed 12-15-85

Plugging Commenced 11-5-86

Plugging Completed 11-6-86

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR McGinness Oil Co.

ADDRESS 1026 Union Center Bldg. Wichita, Ks.

PHONE # 316 267-6065 OPERATORS LICENSE NO. _____

Character of Well oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4670'

Show depth and thickness of all water, oil and gas formations. Perfs 4578-80
4566-72

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0		8 5/8"		0
				5 1/2"		71 fts.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Nov. 5, 1986--Dumped 150 gallons of sand in well. Sand fillup 4445'.

Nov. 6, 1986--Dumped 5 sx. cement, shot off casing, pulled 71 fts. of 5 1/2" casing.

Dec. 4, 1986--700# max, 500# SIP 2:25-3:00 P.M.

Plugged with 3 hulls, 10 gel, 50 sx, 10 gel, 1 hull, 1 plug, 125 sx. cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service, Inc. License No. 5893

Address Box 847 Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Pratt


Julia Berry

plugging contractor
 STATE CORPORATION COMMISSION

~~XXXXXX~~ of above-described well, being first duly sworn on oath, says: DEC 12 1985
 I have knowledge of the facts, statements, and matters herein contained and 12-12-86
 the log of the above-described well as filed that the same are true and WICHITA, KANSAS
 correct, so help me God.

(Signature) Julia Berry

(Address) Box 847 Pratt, Kansas



SUBSCRIBED AND SWORN TO before me this 8th day of December, 1986

Dorothy M. Furgason
 Notary Public

My Commission expires: February 6, 1989