

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21.626-00-00

LEASE NAME Larrison

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

2310 ⁰¹²³ Ft. from S Section Line

2310 ⁰⁸⁰⁵ Ft. from E Section Line

LEASE OPERATOR Vincent Oil Corporation

SEC. 34 TWP. 29 RGE. 13 (E or (W)

ADDRESS 125 N. Market - Suite 1110, Wichita, Ks. 67202

COUNTY Pratt

PHONE# (316) 262-3573 OPERATORS LICENSE NO. 5004

Date Well Completed 7-1-85

Character of Well D&A

Plugging Commenced 7-1-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-1-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4700'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	432	8 5/8"	6-19-85	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged well with 145 sxs 60/40 poz, 6% gel as follows: 750'-50 sxs; 430'-50 sxs; 40'-10 sxs with solid bridge; mousehole-10 sxs; rathole-15 sxs; water well-10 sxs. Job by BJ-Titan Services. Complete at 7:50 p.m. on July 1, 1985.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. 5149

Address P. O. Box 329, Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Pratt, ss.

Arnie Little (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Arnie Little

(Address) P. O. Box 329, Pratt, Kansas 67124

SUBSCRIBED AND SWORN TO before me this 22nd day of July, 19 85

Mary J. Tjaden RECEIVED
Notary Public STATE CORPORATION COMMISSION

My Commission Expires: 3/22/88



07-23-85
JUL 23 1985
Form CP-4
Revised 08-84
CONSERVATION DIVISION
Wichita, Kansas



Oilfield Services, Inc.

- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

DRILLER'S WELL LOG

Larrison #1
 C NW NW SE Sec. 34-29S-13W
 Pratt County, Kansas
 Commenced: 6-18-85
 Completed: 7-1-85
 API #15-151-21,626
 Operator: Vincent Oil Corporation

Depth		Formation	Remarks
From	To		
0	40	Sand	Ran 10 joints (422') new, 23#, 8 5/8" surface casing. Set at 432' with 150 sxs Lite, 3% cc, 100 sxs Class A, 2% gel, 3% cc. Cement did circulate. Job by Sun Cementing. Job complete at 6:30 a.m. on June 19, 1985.
40	845	Sand, Red Bed	
845	1000	Red Bed	
1000	1525	Sand, Red Bed	
1525	1898	Red Bed, Shale	
1898	3430	Shale	
3430	4633	Lime, Shale	
4633	4700	Arbuckle T.D.	RTD 4700' Plugged well with 145 sxs 60/40 poz, 6% gel as follows: 750'-50 sxs; 430'-50 sxs; 40'-10 sxs with solid bridge; mousehole-10 sxs; rathole-15 sxs; water well-10 sxs. Job by BJ-Titan Services. Complete at 7:50 p.m. on July 1, 1985. State Plugger was out of the Dodge City, Kansas office.

STATE OF KANSAS)
) ss
 COUNTY OF PRATT)

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

Arnie Little
 ARNIE LITTLE, VICE-PRESIDENT



Mary L. Tjaden
 NOTARY-PUBLIC

My Commission Expires:
3/22/88

RECEIVED
 STATE CORPORATION COMMISSION

JUL 23 1985