

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Form CP-4

WELL PLUGGING RECORD

NORTH

|  |  |  |  |
|--|--|--|--|
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |

Locate well correctly on above Section Plat

Pratt County. Sec. 34 Twp. 29 Rge. 13 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines NE SW SE  
Lease Owner Great Bend Pipe & Supply Company, Inc.  
Lease Name Laroson-Blaine Well No. 1  
Office Address Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 4-26-65 19  
Plugging completed 4-28-65 19  
Reason for abandonment of well or producing formation Depleted.  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving  
Producing formation Depth to top Bottom Total Depth of Well 4610 Feet  
Show depth and thickness of all water, oil and gas formations.

| OIL, GAS OR WATER RECORDS |         |      |    |        | CASING RECORD |            |
|---------------------------|---------|------|----|--------|---------------|------------|
| FORMATION                 | CONTENT | FROM | TO | SIZE   | PUT IN        | PULLED OUT |
|                           |         |      |    | 8-5/8" | 886'          | None       |
|                           |         |      |    | 4-1/2" | 4604'         | 3792'      |
|                           |         |      |    |        |               |            |
|                           |         |      |    |        |               |            |
|                           |         |      |    |        |               |            |
|                           |         |      |    |        |               |            |
|                           |         |      |    |        |               |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, sanded hole to 4390' and dumped 3 sacks of cement @ 4390' with dump bailer. Pulled 4 1/2" casing, mudded hole to 275', set rock bridge to 260' and dumped 25 sacks of cement @ 260'. Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 4 1965  
05-04-65

PLUGGING COMPLETE.

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of April, 1965

My commission expires May 20, 1968  
Milton J. Volin  
Notary Public.

# DRILLERS LOG

#1 Larrison Blaine

CASING RECORD:  
886' of 3-5/8"  
surface casing

COMPANY: Natural Gas & Oil Company  
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: NE SW SE  
Section 34-29S-13W  
Pratt County, Kansas

TOTAL DEPTH:  
4610'

COMMENCED: July 20, 1960  
COMPLETED: August 7, 1960

## FORMATION

## FROM

## TO

## REMARKS

|                 |      |      |
|-----------------|------|------|
| Sand & Gravel   | 0    | 90   |
| Shale           | 90   | 140  |
| Red Bed & Shale | 140  | 230  |
| Red Bed         | 230  | 708  |
| Red Bed & Shale | 708  | 896  |
| Shale & Shells  | 896  | 1650 |
| Lime & Shale    | 1650 | 2065 |
| Lime            | 2065 | 2530 |
| Shale & Lime    | 2530 | 3810 |
| Lime            | 3810 | 4269 |
| Cherty Lime     | 4269 | 4307 |
| Shale           | 4307 | 4310 |
| Lime & Shale    | 4310 | 4402 |
| Lime            | 4402 | 4515 |
| Shale & Sand    | 4515 | 4530 |
| Hard Sand       | 4530 | 4536 |
| Lime & Shale    | 4536 | 4602 |
| Lime            | 4602 | 4610 |

Ran 886' of 3-5/8" surface casing;  
set and cemented at 893' with 450  
sacks of regular cement, 3% gel and  
2% C. C. Plug down @ 1:00 A. M.  
7-22-1960. Circulated cement.

RECEIVED  
STATE CORPORATION COMMISSION

APR 15 1965

CONSERVATION DIVISION  
Wichita, Kansas

Total Depth 4610'

Ran (147 Jts.) 4603' of 4 1/2" casing;  
cemented with 180 sacks of cement.  
Plug down @ 2:45 P. M. 8-6-1960.

STATE OF KANSAS )  
COUNTY OF BARTON ) ss.

I certify that this is a true and correct copy of the above log to the  
best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp  
Charles W. Steincamp, President

Subscribed and sworn to before me this 11th day of August, 1960.

Elaine H. Taylor  
Elaine H. Taylor, Notary Public

My Commission Expires:  
December 14, 1961

AUG 12 1960