


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pratt County, Sec. 33 Twp. 29 Rge. 13W E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines
2310' FSL 1090' FEL (NW NE SE)
Lease Owner Cities Service Co.
Lease Name Lambert R-3 Well No. _____
Office Address Box 300, Tulsa, Ok. 74102
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 12/22/80 _____ 19____
Plugging completed 12/24/80 _____ 19____
Reason for abandonment of well or producing formation _____

Depleted
If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes _____

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4750'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	337	None
				4-1/2"	3869'	3160'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug-set.

Plugged off bottom. Pushed plug to 3745 and ran one barrell sand. Shot and worked pipe at 3290 and got loose at 3160. Plugged well with 6 sacks hulls, 30 sacks gel and 25 sacks cement, 50/50 pos 4% gel 3% cc.

Plugging complete.

12-31-80
DEC 31 1980
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of December, 19 80

My commission expires _____



Joan Kelso
Notary Public.

Operator

Cities Service Company

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.

3

Lease Name

Lambert "B"

Gas

S 33 T 29S R 13 XXX
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand	0	93		
Sand/shale/clay	93	105		
Red Bed/shale	105	934		
Red Bed	935	1150		
Shale/shells	1150	1800		
Lime/shale	1800	1920		
Shale/lime	1920	2270		
Lime/shale	2270	2505		
Shale/lime	2505	2702		
Lime/shale	2702	2827		
Shale/lime	2827	3040		
Lime/shale	3040	3335		
Shale/lime	3335	3530		
Lime	3530	3735		
Lime/shale	3735	3886		
Shale/lime	3886	3970		
Lime	3970	4047		
Lime/shale stks.	4047	4167		
Lime/shale	4167	4245		
Lime	4245	4330		
Lime/Chert	4330	4400		
Lime	4400	4468		
Lime/shale	4468	4545		
Lime	4545	4603		
Simpson lime	4603	4611		
Lime	4611	4750		

RECEIVED
 CONSERVATION COMMISSION
 MAY 17 1960
 CONSERVATION DIVISION
 Wichita, Kansas

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received



Signature C. E. Forrester

Region Petroleum Engineer

Title

May 15, 1979

Date