


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pratt County, Sec. 30 Twp. 29 Rge. 13 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C of NW SE
Lease Owner W. L. Kirkman, Inc.
Lease Name Lambert #1 Well No.
Office Address Pratt, Kansas 67124
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 2/23/77 19
Plugging completed 2/26/77 19
Reason for abandonment of well or producing formation
depleted.
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Metz
Producing formation Depth to top Bottom Total Depth of Well 4800
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	252	none
				5 1/2"	4799	2946'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Sanded to 3025' and ran 5 sacks cement. Shot pipe at 2930',
pulled 79 joints. Squeezed hole with 3 sacks hulls, 15 sacks gel,
released plug and displaced with 125 sacks cement, 50-50 permix.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

MAR 07 1977

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. BARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature)

R. Barrell Kelso
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of February, 19 77

My commission expires



Margaret Melcher
Notary Public.

WELL LOG

B.P. 3400'
PERF 3200'-3202'
SQUEEZED W/175 SACKS 50-50% POZMA
PERF. 3050'-56'
TOP OF CEMENT AT 3000'

LAMBERT #1
C NW SE Sec. 30-29S-13W
Pratt County, Kansas

OPERATOR: GEMINI OIL & GAS CO.
CONTRACTOR: XPLOR DRILLING CO.

COMMENCED: 12-9-75
COMPLETED: 12-22-75

Casing Record: Set 6 joints new 30# 10 3/4" casing @ 252' w/285 sacks common cement, 2% gel, 3% cal. chloride; 132 joints new 5 1/2" casing @ 4799' with 200 sacks 60-40 posmix, 18% salt, 3/4 of 1% CFR2.

FORMATION	FROM	TO	ELEVATION
Surface Soil	0	20	1939 Gr.
Clay & Sand	20	200	1944 D.F.
Red Bed Shale	200	258	1947 K.B.
Sand & Shale	258	300	
Shale	300	1592	
Anhydrite	1592	1598	
Shale w/Lime Streaks	1598	1925	
Shale & Shells	1925	2190	
Shale	2190	2514	
Lime & Shale	2514	4045	
Lime	4045	4800	
R.T.D.	4800		

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

I Certify that this is a true and correct copy of the Driller's Log of the well drilled in the C NW SE of Section 30-29S-13W, Pratt County, Kansas, to the best of my knowledge and belief.

XPLOR DRILLING CO.

FEB 25 1977

B. G. Harrelson
B. G. Harrelson, Office Manager

Subscribed and sworn to before me this 29th day of December, 1975.

MY COMMISSION EXPIRES:
August 25, 1976

Virginia Lee Smith
Virginia Lee Smith, Notary Public

