

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-20,783-0000

LEASE NAME Ora Lambert

WELL NUMBER _____

SPOT LOCATION C SW NE

SEC. 30 TWP. 29 RGE. 13W (E) or (W)

COUNTY Pratt

Date Well Completed _____

Plugging Commenced 3/2/84

Plugging Completed 3/8/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F.G. Holl

ADDRESS 6427 E. Kellogg, Wichita, Ks. 67207

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4777'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10. 3/4	218'	none
				4 1/2"	4776'	2510'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pumped 80 bls salt water to kill well. Pumped 40 sacks cement to 3975'. Shot well at 3900', 3700', 3500', 3300', 3000', 2700', & 2510'. Pulled 66 joints.

Plugged well with 3 hulls, 15 gal, 50 cement, 10 gal, 1 hull, 10 3/4 plug, & 150 sacks 60/40 poz 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

MAR 15 1984
03-15-84
CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 13 day of March, 19 84

My Commission expires:



Irene Hoover
Notary Public

KANSAS DRILLERS LOG

COMPANY F. G. Holl

SEC. 30 T-29S R-13W

FARM Ora Lambert NO. 1-30

LOC. C-SW NE

COUNTY Pratt

ROTARY TOTAL DEPTH 4,777'

COMM. July 5, 1980

COMP. July 18, 1980

CONTRACTOR H-30, Inc. (Rig #11)

ISSUED August 1, 1980

CASING

10 3/4" Set at 218' cemented w/225 sxs cement

8 5/8"

5 1/2"

4 1/2" Set at 4,776' cemented w/250 sxs cement

ELEVATION 1,939' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale and Sand	195'
Red Bed	227'
Red Bed and Shale	880'
Shale	2,730'
Shale and Lime	2,875'
Lime and Shale	3,255'
Lime	3,415'
Lime and Shale	3,780'
Lime	4,725'
Shale	4,777'
Rotary Total Depth	4,777'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

DOTTY L. MORGAN
 NOTARY PUBLIC
 JOHNSON COUNTY, KANSAS
 My Appointment Expires Sept 14, 1980


 Dean Britting

State of Kansas)
) ss:
 County of Johnson)

Subscribed and Sworn to before me a Notary Public in and for said county and state this 4th day of August, 1980.


 Dotty L. Morgan - Notary Public

My Commission Expires: September 14, 1980