

TATE OF KANSAS  
TATE CORPORATION COMMISSION  
30 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-21,299-00-00

LEASE NAME Stapleton "A"

WELL NUMBER 1-25

2970' Ft. from (S) Section Line

2310' Ft. from (E) Section Line

SEC. 25 TWP. 24S RGE. 17W (E) or (W)

COUNTY Edwards

Date Well Completed 12-17-87

Plugging Commenced 08-01-2000

Plugging Completed 08-02-2000

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR F.G. Holl Company, L.L.C.

ADDRESS P.O. BOX 780167, Wichita, Kansas 67278-0167

PHONE (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 17th, 2000 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Mississippi/Kinderhook Depth to Top 4369' Bottom 4407' T.O. 4520'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	302'	0
				4 1/2"	4518'	2343'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section. Sand at 4303'. Bailed 4 sacks of portland cement. Shot at 2527'. Shot at 2343'. Pulled to 1200. Pumped 12 gel 50 sacks, 3 gel. Pulled to 340'. Pumped 50 sacks. Pulled to 40'. Pumped 10 sacks. Laid last joint down. Hole stayed full.

Name of Plugging Contractor Quality Well Service License No. 31925

Address 415 East Main Street, Sterling, Kansas 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl Company, L.L.C.

STATE OF Kansas COUNTY OF Sedgwick, ss.

W. Bryce Bidleman (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) W. Bryce Bidleman

(Address) Wichita, Kansas 67278-0167

SUBSCRIBED AND SWORN TO before me this 24th day of August, 2000 XXXXX

Sharon J. Clark RECEIVED  
Notary Public STATE CORPORATION COMMISSION

My Commission Expires: 3-16-03

