

STATE OF KANSAS
ATE CORPORATION COMMISSION
3 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

API NUMBER 15-047-20,942-00-00

LEASE NAME Belva Montgomery

WELL NUMBER 2

330 Ft. from N Section Line

330 Ft. from E Section Line

SEC. 24 TWP. 24 SRGE. 16W (E) or (W)

COUNTY Edwards

Date Well Completed _____

Plugging Commenced 11-30-01

Plugging Completed 12-03-01

RECEIVED

DEC 21 2001

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Vess Oil Corporation

ADDRESS 8100 E. 22nd. St. N. #300 Wichita, Kansas 67226

PHONE#(316) 682-1536 OPERATORS LICENSE NO. 5030

Character of Well Oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4120'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	394'	None
				4-1/2"	4120'	2300'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material is used, state the character of same and depth placed, from _____ feet to _____ feet each section.
Plugged off bottom with sand to 3700' and 4 sx. cement. Shot casing @2300', pulled up to 1050', pumped 1050', pumped 15 sx. gel, 50 sx. cement, pulled up to 440', pumped 50 sx. cement, pulled up to 40' and circulated 30 sx. cement, 60/40 pos. 6% gel.
Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Vess Oil Corporation

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 19th day of December, 2001

[Signature]
Notary Public

My Commission Expires:

