

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-20548-00-00

LEASE NAME Bisel

WELL NUMBER 2

990 Ft. from S Section Line

330 Ft. from <sup>W</sup>E Section Line

SEC. 1 TWP. 26S RGE. 16W (E) or (W)

COUNTY Edwards

Date Well Completed \_\_\_\_\_

Plugging Commenced 3-26-01

Plugging Completed 3-27-01

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR PRATER OIL & GAS OPERATIONS, INC.

ADDRESS 906 William Way Pratt, Kansas 67124

PHONE# (620) 672-3501 OPERATORS LICENSE NO. 31000

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4446'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD RECEIVED  
STATE CORPORATION COMMISSION

| Formation | Content | From | To | Size   | Put in | Pulled out                               |
|-----------|---------|------|----|--------|--------|--|
|           |         |      |    | 8-5/8" | 376'   | None                                     |
|           |         |      |    | 5-1/2" | 4433'  | 2310'                                    |
|           |         |      |    |        |        | CONSERVATION DIVISION<br>Wichita, Kansas |

APR 19 2001

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s  
Plugged off bottom with sand to 3750' and 5 sks. cement. Shot pipe @2500' and 2310', pulled up to 1050', pumped 15 sks. gel, 50 sks. cement, pulled up to 400', pumped 50 sks. cement, pulled up to 40', topped off with 10 sks. cement, 60/40 pos. 6% gel  
Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Prater Oil & Gas Operations, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed t the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 17th day of April, 2001

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_



[Handwritten initials]