

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 2078
WICHITA, KS 67202

RECEIVED

FEB 20 2002

KCC WICHITA

WELL PLUGGING RECORD
K.A.R. 82-3-117

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

API NUMBER 15-047-20551-00-01
15-07205510000

LEASE NAME Crockett

WELL NUMBER 4

4770 Ft. from S Section Line

4620 Ft. from E Section Line

SEC 35 TWP 26S RGE 17 (W)

COUNTY Edwards

Date Well Completed 8/29/79

Plugging Commenced 2/06/02

Plugging Completed 2/07/02

LEASE OPERATOR White & Ellis Drilling, Inc.

ADDRESS P.O. Box 48848

PHONE # 316-263-1102

Character of Well Injection

(Oil, Gas, D & A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2/06/02 (date)

by Richard Lacy (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? Already on file

Producing Formation Pleasanton Depth to Top 4370 Bottom 4380 T.D. 4450

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Pleasanton	Oil	0	362	8 5/8"	362	0
		0	4452	4 1/2"	4452	2430

Describe in detail the manner in which the well was plugged, indicating where the mud was fluid placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Pulled csg to 1130' - pumped 50 sx 60/40 poz w/ 6% gel from 1130' to 950'

Pulled csg to 390' - pumped 50 sx 60/40 poz w/ 6% gel from 390' to 200'

Pulled csg to 40' - pumped 30 sx 60/40 pox w/ 6% gel from 40' to surface.

CIBP @ 4265'. Dumped 2 sxs cement on CIBP w/ dump bailer

Name of Plugging Contractor Mike's Testing and Salvage License No. 31529

Address P.O. Box 467; Chase Ks. 67524-0209

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: White & Ellis Drilling, Inc.

STATE OF KANSAS COUNTY OF Sedgwick, ss.


Charles Schmidt (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Charles Schmidt

(Address) 1321 W. 93rd N., Valley Center, KS 67147

SUBSCRIBED AND SWORN TO before me this 18 day of February 2002

Marsha Breitenstein
Notary Public



My Commission Expires: 9-15-2003

Handwritten initials/signature

RECEIVED

FEB 20 2002

KCC WICHITA

ALLIED CEMENTING CO., INC.

08943

Federal Tax I.D.# 48-0727860

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Medicine Lodge

DATE <u>2-07-02</u>	SEC <u>35</u>	TWP <u>26S</u>	RANGE <u>7W</u>	CALLED OUT <u>10:00 Am</u>	ON LOCATION <u>12:00 pm</u>	JOB START <u>1:15 pm</u>	JOB FINISH <u>2:30 pm</u>
LEASE <u>Crockett</u>	WELL # <u>4</u>	LOCATION <u>Trousdale, South to</u>		COUNTY <u>Edwards</u>	STATE <u>Ks.</u>		
OLD OR NEW (Circle one)				<u>Stop sign, 1w, 35, 3w, 12s,</u>			

CONTRACTOR Mike T+S OWNER White + Ellis Drgl

TYPE OF JOB CHP

HOLE SIZE 7 7/8 T.D. _____

CASING SIZE 4B DEPTH 1130'

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX 100 MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT Fresh

EQUIPMENT _____

PUMP TRUCK # 353 CEMENTER Carl Ballinger

BULK TRUCK # 364 DRIVER Chris Longford

BULK TRUCK # _____ DRIVER _____

CEMENT AMOUNT ORDERED

COMMON 78 @ 6.65 518.70

POZMIX 52 @ 3.55 184.60

GEL 22 @ 10.00 220.00

CHLORIDE _____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

HANDLING 152 @ 1.10 167.20

MILEAGE 152 x 30 @ .04 182.40

TOTAL 1272.90

REMARKS:

1st Plug 1130' Load Hole w/ 15sx
Grk water + Pump 50 sx Cement

2nd Plug 330' Pump 50 sx Cement

3rd Plug 40' to surface Pump 30 sx Cement

SERVICE

DEPTH OF JOB 1130'

PUMP TRUCK CHARGE _____ 475.00

EXTRA FOOTAGE @ _____

MILEAGE 30 @ 3.00 90.00

PLUG @ _____

_____ @ _____

TOTAL 565.00

CHARGE TO: White + Ellis Drgl

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

TOTAL _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]

TAX 117.63

TOTAL CHARGE 1955.53

DISCOUNT 183.79 IF PAID IN 30 DAYS

1771.74

PRINTED NAME Monte J Andrews

Net \$ 1771.74



CEMENTING LOG

STAGE NO.

Date 2-07-02 District Medicine Lake Ticket No. 08943
 Company White + Ellis Drig Rig Mikes F+S
 Lease _____ Well No. _____
 Country Edwards State Ks
 Location Moundsdale S, to step Field 35-265-17u
 Sign, 1w, 3g, 3w, 1/2S into
 CASING DATA: PTA Squeeze
 Surface Intermediate Production Liner
 Size 4 1/2 Type _____ Weight _____ Collar _____

RECEIVED

FEB 20 2002

KCC WICHITA

Casing Depths: Top _____ Bottom _____

Drill Pipe: Size _____ Weight _____ Collars _____
 Open Hole: Size _____ T.D. _____ ft. P.B. to _____ ft.

CAPACITY FACTORS:
 Casing: Bbls/Lin. ft. .2159 Lin. ft./Bbl. 62.70
 Open Holes: Bbls/Lin. ft. _____ Lin. ft./Bbl. _____
 Drill Pipe: Bbls/Lin. ft. _____ Lin. ft./Bbl. _____
 Annulus: Bbls/Lin. ft. .0406 Lin. ft./Bbl. 24.64
 Bbls/Lin. ft. .0440 Lin. ft./Bbl. 22.72
 Perforations: From _____ ft to _____ ft Amt. _____

CEMENT DATA:
 Spacer Type: 15 sx Gel
 Amt. _____ Skys Yield _____ ft³/sk Density _____ PPG
 LEAD: Pump Time _____ hrs. Type 60:40:6
 Excess _____
 Amt. 130 Skys Yield 1.58 ft³/sk Density 13.8 PPG
 TAIL: Pump Time _____ hrs. Type _____
 Excess _____
 Amt. _____ Skys Yield _____ ft³/sk Density _____ PPG
 WATER: Lead 7.8 gals/sk Tail _____ gals/sk Total _____ Bbls.
 Pump Trucks Used 352 Dave Felio
 Bulk Equip. 364 Chris Lungstord

COMPANY REPRESENTATIVE Monte Andrews CEMENTER Carl Bolding

TIME	PRESSURES PSI		FLUID PUMPED DATA			REMARKS
	AM/PM	DRILL PIPE CASING	ANNULUS	TOTAL FLUID	Pumped Per Time Period	
<u>12:00 pm</u>						<u>Rig up</u>
						<u>1st Plug 1130'</u>
<u>1:15 pm</u>	<u>100</u>		<u>30</u>	<u>30</u>	<u>5</u>	<u>Load Hole w/ 15 sx Gel</u>
	<u>100</u>		<u>44</u>	<u>14</u>	<u>6</u>	<u>Pump 50 sx Cement</u>
			<u>54</u>	<u>10</u>	<u>4</u>	<u>Displace with 10 Bbls Fresh</u>
						<u>2nd plug 390'</u>
	<u>100</u>		<u>59</u>	<u>5</u>	<u>4</u>	<u>Load Hole w/ Fresh</u>
	<u>100</u>		<u>73</u>	<u>14</u>	<u>5</u>	<u>Pump 50 sx cement</u>
			<u>75</u>	<u>2</u>	<u>4</u>	<u>Displace with 2 Bbls Fresh</u>
						<u>3rd plug 40'</u>
<u>2:30 pm</u>			<u>83.5</u>	<u>5.5</u>	<u>4</u>	<u>Circulate cement to surface w/ 30 sx Cement</u>