

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

15-151-21459-0001
API NUMBER Docket# 23720 07-30-84

LEASE NAME Starkey SWD

WELL NUMBER SWD

TYPE OR PRINT
NOTICE: Fill out completely
and return to Coast. Div.
office within 30 days.

660 Ft. from (S) Section Line

4620 Ft. from (E) Section Line

SEC. 31 TWP. 27S RGE. 15 (E) or (W)

COUNTY Pratt

Date Well Completed 07-30-84

Plugging Commenced 02-03-95

Plugging Completed 02-03-95

LEASE OPERATOR Oil Producers, Inc. of Kansas

ADDRESS P.O. Box 8647, Wichita, Kansas 67208

PHONE# (316) 672-6373 OPERATORS LICENSE No. 8061

Character of Well SWD

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 02-03-95 (date)

by Steve Rfeifer (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, is well log attached?

Producing Formation Shawnee Lansing Depth to Top 3842-4194 Bottom 3914 T.D. 4740

Mississippi 4622 4630

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0		4 1/2		
	Casing	0		4 3/8		2655.95

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug was used, state the character of same and depth placed, - from feet to feet each set. Sanded off bottom to 4154', dumped 4 sacks of cement, pulled 2655' 5 1/2" casing. Called out Allied Cementing, mixed 300 lbs. hulls, 10 sks of gel, 50 sks of cement, 10 sks of gel 100 lbs. of hulls, released plug, and pumped 150 sks of cement. Max PSI 600 lbs. Shut in 200 lbs.

Name of Plugging Contractor D.S. & W. Well Servicing, Inc. License No. 6901

Address P.O. Box 231, Claflin, Kansas 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oil Producers, Inc. of Kansas

STATE OF Kansas COUNTY OF Barton, ss.

Arthur P. Strube (Employee of Operator or Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as inserted in the same are true and correct, so help me God.

(Signature) Arthur P. Strube


(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED AND SWORN TO before me this 6th day of February, 19 95

Karlynn K. Beck
Notary Public

My Commission Expires: 09-28-98

USE ONLY ONE SIDE OF EACH FORM



Form CP-4
Revised 05-88