

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Pratt County, Sec. 12 Twp. 27 Rge. (E) 15 (W)

Location as "NE/CNW/SW" or footage from lines NE-NE-SW
Lease Owner United States Hydrocarbon Co.
Lease Name Halper Well No. 2
Office Address Wichita, Kans.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 9-19-72
Plugging completed 9-21-72
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation Depth to top Bottom Total Depth of Well 4520 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 1/2 | 327 | None |
| | | | | 4 1/2 | 4519 | 2250 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sand back to 4450ft.- dump 4 sax cement - pull pipe - Globe Cementing Co. pumped 2 sax hulls, 15 sax gel & 100 sax cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 7 - 1972 12-7-72
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ralph Comstock Pipe Pulling, Inc. Permit # 490
Address Stafford, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.
A. J. Greenbaum (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) [Signature]
P.O. Box 11027
Washington St. Station, Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of December, 1972

My commission expires

Kathleen A. Matzen
STATE NOTARY PUBLIC
Sedgwick County, Kansas
Commission Expires Sept. 16, 1975

[Signature]
Notary Public.

DRILLERS LOG

#2 Halper

CASING RECORD: Ran 327.69' of new 8-5/8" surface casing. COMPANY: United States Hydrocarbon Company DESCRIPTION: C/SW SE Section 12-278-15W Pratt County, Kansas
 CONTRACTOR: Strata Drilling, Inc.
 TOTAL DEPTH: 4520' COMMENCED: December 17, 1967 ELEVATION: 2035' DT
 COMPLETED: January 1, 1968

| <u>FORMATION</u> | <u>FROM</u> | <u>TO</u> | <u>REMARKS</u> |
|--------------------|-------------|-----------|--|
| Sand, Clay & Shale | 0 | 360 | Ran 327.69' of new 8-5/8" surface casing; set and cemented at 327.69' with 220 sacks of common cement and 2 1/2 gal. Plug down at 10:30 A. M. December 18, 1967. |
| Shale & Shells | 360 | 926 | |
| Anhydrite | 926 | 946 | |
| Shale | 946 | 2030 | |
| Shale & Lime | 2030 | 3940 | |
| Lime | 3940 | 4354 | |
| Lime & Chert | 4354 | 4450 | |
| Lime | 4450 | 4520 | |

Total Depth 4520'

RECEIVED
STATE CORPORATION COMMISSION

DEC 11 1972

CONSERVATION DIVISION
Wichita, Kansas

Ran 4519' of new 4 1/2"; set and cemented at 4519' with 250 sacks of 60-40 poxmix, salt saturated with 15 barrels salt flush ahead of cement. Plug down at 11:30 P. M. January 1, 1968.

STATE OF KANSAS }
COUNTY OF BARTON } ss:

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Jim B. McWilliams
Jim B. McWilliams, Secy-Treas.

Subscribed and sworn to before me this 3rd day of January, 1968.

Elaine H. Taylor
Elaine H. Taylor, Notary Public

My Commission Expires:

December 14, 1969

