

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

PRATT County, Sec. 12 Twp. 27 Rge. 15 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE, NE, NW

Lease Owner ROONEY-SEIGFRIED & THOMAS

Lease Name R. WARD Well No. 1

Office Address BOX 324 - GREAT BEND, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed 5-24 1954

Application for plugging filed 5-24 1954

Application for plugging approved 5-24 1954

Plugging commenced 5-24 1954

Plugging completed 5-24 1954

Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. RIVES

Producing formation Depth to top Bottom Total Depth of Well 4730 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner	Marker	3779		8 5/8" 28#	1009.25	None
Lansing Kansas City	Dry	3962				
Mississippi	Dry	4148				
Kinder Hook	Dry	4479				
Viola	Dry	4548				
Simpson	Dry	4591				
Arbuckle	Dry	4678	4730			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole was filled with heavy mud to 300 feet, set plug and run 20 sacks of cement through drill pipe. Mud to 35', set plug and run 10 sacks of cement.

Name of Plugging Contractor SCHAFER DRILLING COMPANY  
Address BOX 350 - PRATT, KANSAS

STATE OF Kansas, COUNTY OF Butte, ss.

W. A. Ferguson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) W. A. Ferguson

(Address)

SUBSCRIBED AND SWORN TO before me this 1 day of June, 1954

My commission expires May 3, 1957

Notary Public.



DRILLER'S LOG

R. WARD #1-----ROONEY-SEIGFRIED & THOMAS  
PRATT COUNTY, KANSAS

0-200	Sand & Surface Clay
200-230	Water Sand
230-300	Sand & Gravel
300-630	Clay & Red Bed
630-815	Red Bed & Shell
815-990	Red Bed, Shale & Shells
990-1002	Anhydrite
1002-1114.5	Shale
1114.5-1725	Shale & Lime Shell
1725-1850	Shale & Lime
1850-2017	Shale, Lime & Sand
2017-2210	Lime
2210-2275	Salt & Shale
2275-3585	Shale & Lime
3585-3625	Lime
3625-3883	Shale & Lime
3883-3935	Shale & Shells
3935-3972	Shale
3972-4030	Shale & Lime
4030-4280	Lime
4280-4412	Shale & Lime
4412-4448	Shale
4448-4520	Shale & Lime
4520-4536	Shale, Lime & Chert
4536-4538	Shale
4538-4591	Shale & Lime
4591-4630	Shale, Lime & Chert
4630-4670	Shale & Sand
4670-4678	Shale & Lime
4678-4730	Arbuckle Lime
4730	TOTAL DEPTH

STATE OF KANSAS: COUNTY OF Pratt :SS:

I certify that the above is true and correct as being taken from the daily drilling reports of the R. Ward #1.

SCHAFFER DRILLING COMPANY

By W.A. Boyson

Subscribed and sworn to before me this 26th day of May 1954.

**PLUGGING**  
 T11 SEC. 12 T. 27 R. 15W  
 W001 PAGE 36 LINE 41

Mabel Pugh  
Notary Public

My commission expires May 3, 1957