


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Stanton County, Sec. 20 Twp. 27S Rge. (E) 40 (W)  
Location as "NE/CNW/SW" or footage from lines C SW/4  
Lease Owner Kansas Petroleum, Incorporated  
Lease Name Cross Well No. 1  
Office Address 1620 KSB&T Building, Wichita, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 30, 19 70  
Application for plugging filed (verbally) December 30, 19 70  
Application for plugging approved (verbally) December 30, 19 70  
Plugging commenced December 30, 19 70  
Plugging completed 1:00 p.m. December 30, 19 70  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves, Sublette, Ks.  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2600 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	565'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud. Set first plug at 575' with 35 sx. cement pumped through drill pipe by Dowell Div. Set top plug at 40' w/10 sx. cement. Job complete at 1:00 p.m. 12-30-70.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 5 1971  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.  
Address 801 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Jerry A. Langrehr (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrehr  
801 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of January, 19 71

My commission expires November 12, 1973

Sue J. McCoy  
Notary Public.

CONTRACTOR'S WELL LOG

OPERATOR:	Kansas Petroleum, Incorporated
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	CROSS #1
LOCATION:	C SW/4 Sec. 20-27S-40W Stanton County, Kansas
SPUD DATE:	December 26, 1970
COMPLETION DATE:	December 30, 1970

0	50	Clay
50	105	Sand
105	1280	Shale
1280	1480	Salt
1480	1560	Sand
1560	1697	Lime & Shale
1697	1709	Anhydrite
1709	2362	Lime and Shale
2362	2465	Shale & Lime
2465	2600	Lime and Shale
	2600	Rotary Total Depth

Set 565' of 8-5/8" surface w/300 sx. cement. Cement circulated. Plug was down at 8:30 p.m. 12-26-70.  
Dry and Abandoned

STATE OF KANSAS        )  
                              ) SS  
COUNTY OF SEDGWICK )

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 5 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Jerry A. Langrehr, President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the CROSS #1, C SW/4, Sec. 20-27S-40W, Stanton County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr  
Jerry A. Langrehr  
President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 4th day of January, 1971.

Sue J. McCoy  
Sue J. McCoy, Notary Public

My Commission Expires:

November 12, 1973