

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stanton

County, Sec. 15 Twp. 27 Rge. ~~26~~ 41 (W)

Location as "NE/CNW/SW" or footage from lines C NE

Lease Owner Carl B. Anderson, Sr.

Lease Name Raney Well No. 1

Office Address 3814 N. Santa Fe Oklahoma City, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed January 29 1957

Application for plugging filed February 6 1957

Application for plugging approved 19

Plugging commenced January 30 1957

Plugging completed January 30 1957

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation None Depth to top Bottom Total Depth of Well 5407 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand	Water	2405	2420	8 5/8"	1867	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

This well was drilled to a total depth of 5407' with no oil or gas shows.

The Drilling Contractor on the well secured permission from M. A. Rives to plug well. We set a cement plug @ 600' with 35 sacks cement and with 2% Cacl and another cement plug @ 35' with 12 sacks cement in the 8 5/8" surface casing.

Location of these plugs are surface to 35' and from 505 to 600' inside the surface casing which was set @ 1867 and circulate from top to bottom with cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor
Address

STATE OF Oklahoma, COUNTY OF Oklahoma, ss. Raymond Price

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Raymond Price Asst. Prod. Supt.
3814 N. Santa Fe Oklahoma City, Oklahoma
(Address)

SUBSCRIBED AND SWORN to before me this 7th day of February, 1957

My commission expires 12-15-59

La Nell De Stuss Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

FEB 12 1957 2-12-57

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEG 15 T. & R. 41W
BOOK PAGE 127 L.I.E. 29

WELL LOG

RANEY No. 1
C NE Sec. 15-27S-41W
Stanton County, Kansas

OPERATOR: CARL B. ANDERSON, SR.

CONTRACTOR: Garr-Woolley Company

DRILLING STARTED: December 27, 1956

DRILLING COMPLETED: January 29, 1957

FORMATIONS

Clay & sand	0	460
Shale, redbeds & sand	460	800
Sand, lime shells, redbeds	800	940
Shale, redbeds & sand	940	1037
Sand	1037	1100
Redbeds	1100	1221
Shale & sand	1221	1380
Sand & redbeds	1380	1466
Sand & shale	1466	1599
Redbeds & sand	1599	1632
Lime & sand	1632	1678
Hard sand	1678	1711
Hard sand & lime	1711	1830
Hard sand	1830	1841
Sand & shale	1841	1865
Lime	1865	1875
Shale & shells	1875	2006
Redbeds & shells	2006	2168
Lime & shale	2168	2252
Shale & sand	2252	2407
Shale & lime	2407	2711
Lime	2711	2851
Lime & shale	2851	2917
Lime	2917	2985
Lime & shale	2985	3383
Lime & chalk	3383	3482
Lime	3482	4473
Lime & shale	4473	4515
Lime	4515	4592
Lime & shale	4592	4611
Lime w/shale streaks	4611	4756
Lime	4756	4786
Lime & shale	4786	4862
Lime	4862	4875
Lime & shale	4875	4964
Shale	4964	5228
Lime	5228	5247
Sand & shale	5247	5289
Lime & shale	5289	5299
Lime	5299	5405 - T.D.

Casing Record

1867' of 8-5/8" 24# protection string cemented w/1100 sacks -
circulated from top to bottom.

AFFIDAVIT

I, the undersigned, being first duly sworn upon oath, state that this well log is true, correct and complete according to the records of this office and to the best of my knowledge and belief.

CARL B. ANDERSON, SR.

BY: M. R. Joy

Subscribed and sworn to before me this 7th day of February, 1957.

My Commission Expires:
December 15, 1959.

PLUGGING
FILE SEC 15 T. 27 R. 41W
BOOK PAGE 127 LINE 29

RECEIVED
STATE CORPORATION COMMISSION
La. Nell
Notary Public

FEB 12 1957

CONSERVATION DIVISION
Wichita, Kansas