

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stanton County. Sec. 27 Twp. 27 Rge. 41 (E) (W)

Location as "NE/CNW%SW%" or footage from lines NE NE NE

Lease Owner Musgrove Petr / Sierra Petroleum - Contr.

Lease Name WINGER #1 Well No. 1

Office Address /208 Petr. Bldg., Wichita, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) dry

Date well completed 10/17/1959

Application for plugging filed 10/17/1959

Application for plugging approved 10/17/1959


Plugging commenced 10/17/1959

Plugging completed 10/17/1959

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Rives, Garden City, Ks.

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5487 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1724	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging Report

Filled hole with heavy mud from 5487 up to 655'. Set bridge using 1/3 sks hulls, wood plug and 25 sks cement through drill pipe. Filled hole with heavy mud up to 30' below bottom of cellar. Set bridge using 1 sks hulls, wood plug and 10 sacks cement to cellar 0. Job completed 6:30 am 10/17/59

RECEIVED
STATE CORPORATION COMMISSION
OCT 29 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sierra Petroleum Co., Inc.
Address Russell, Kansas

STATE OF KANSAS COUNTY OF RUSSELL, ss.

C. T. Honaker (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker

(Address) _____

SUBSCRIBED AND SWORN TO before me this 28th day of October, 19 59

Margie Casper
Notary Public.

My commission expires 1-30-61.



Musgrove Petroleum - Operator

Sierra Petroleum - Contr.

WINGER #1

NE NE NE Sec 27-27S-41W
Stanton County, Kansas

Total Depth: 5487

Elev: 3228 KB

Comm: 9/22/59

Comp: 10/17/59

Casing:

Cement:

8 5/8 @ 1724

with 700 sacks

FORMATION	DEPTH
Surface Sand	20
Sand & Shale	300
Shale	500
Red Bed	930
Anhydrite & shale	1265
Red Bed	1405
Red Bed & Shale	1688
Red Bed & Gyp	1718
Anhydrite	1726
Shale & sand	2100
Shale	2370
Lime & Sandy Shale	2400
Shale & Lime	3840
Lime	4020
Lime & Shale	4160
Lime	4647
Lime & Shale	4700
Lime	4953
Lime & shale	5016
Lime, shale & sand	5081
Sand & Shale	5100
Shale	5190
Shale & lime	5270
Shale	5310
Shale & sand	5328
Sand	5341
Sand, shale & lime	5387
Shale & Lime	5428
Lime	5487

Tops:	FORMATION	DEPTH
	Anhydrite	1718
	Heebner	3685
	Toronto	3722
	Lans. K.C.	3747
	Base K.C.	4336
	Marmaton	4364
	Cherokee	4554
	Morrow Shale	5045
	Keys	5286
	Chester	5340
	St. Geneve	5353
	St. Louis	5447

RECEIVED
STATE COLPITATION COMMISSION
OCT 29 1959
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

C. D. Harker

Subscribed and sworn to before me this 28th day of October, 1959.

Margie Cooper
Notary Public

My commission expires: 1-30-61.