


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Stanton County. Sec. 25. Twp. 27S. Rge. (E) 41 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines CSW $\frac{1}{4}$ NE $\frac{1}{4}$
Lease Owner United Producing Co., Inc.
Lease Name Carl Lane Well No. 1
Office Address Box 127 - Satanta, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 17, 1951 19
Application for plugging filed September 16, 1951 - Verbal 19
Application for plugging approved October 4, 1951 - See Below 19
Plugging commenced September 17, 1951 19
Plugging completed Not completely plugged - See Below 19
Reason for abandonment of well or producing formation Not commercial

NORTH



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well R. J. Phillippe
Producing formation None Productive Depth to top 2256 RB. Bottom 6998 RB. Total Depth of Well 6998 RB Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD


| Formation | Content | From | To | Size | Put In | Pulled Out |
|----------------------------|------------------|------|--------|------------------|------------|------------|
| Surface clay & Fresh Water | Snd. Fresh Water | | 290' | 16" OD | 328' | None |
| Chase Series - Salt Water | & Salt Mass | 290 | 2225 | 10 3/4" OD | 2443' | None |
| Hollenburg | Barren | 2225 | 2227RB | Cased With Above | 10 3/4" OD | |
| Herington | Semi-Barren | 2256 | 2267 | | " | |
| Krider | " " | 2267 | 2276 | | " | |
| Winfield | Salt Water | 2301 | 2331 | | " | |
| Upper Ft. Riley | " " | 2376 | 2391 | | " | |
| Lower Ft. Riley | " " | 2419 | 2457 | | " | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Formation, Continued:

Florence Barren 2481 to 2507 Open Hole
Lansing-KC Barren & Salt Water 3712 to 5088 Open Hole
Morrow Salt Water 5296 to 5328 Open Hole
Mississippi Barren & Salt Water 5328 to 6195 Open Hole
Arbuckle " & " " 6255 to 6978 " "
Reagan Barren 6978 - Base Not Drilled " "

Plugging Data:
6998 to 6350 Drilling Mud
6350 to 6148 Cement
6148 to 5360 Drilling Mud
5360 to 5140 Cement
5140 to 3750 Drilling Mud
3750 to 3619 Cement
3619 to 2500 Drilling Mud
2500 to 2246 Cement
2246 to 15 Drilling Mud - All measurements from rotary bushing-



11 feet above ground level - 15 feet above bottom cellar temporarily abandoned - When permanently abandoned, plugging will be completed in accordance with state requirements and another plugging record made.

(If additional description is necessary, use BACK of this sheet)

- Correspondence regarding this well should be addressed to Arthur H. Robinson - Dist. Supt. - United
Address: Producing Co., Inc. - Box 127, Satanta, Kansas

STATE OF Kansas, COUNTY OF Haskell, ss:

Arthur H. Robinson (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Arthur H. Robinson

Satanta, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 12 day of October, 1951

William B. Claunch
Notary Public.

My commission expires August 30, 1952