

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH

X			

Locate well correctly on above
Section Plat

Stanton County, Sec. 24 Twp. 27S Rge. 41 (E) W (W)
 Location as "NE/CNW/SW" or footage from lines 660' fr. South and 660' fr. West line
 Lease Owner Burk Royalty Co.
 Lease Name Lowe Well No. 1
 Office Address 800 Oil & Gas Bldg., Wichita Falls, Texas 76301
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed 4/10/69 19
 Application for plugging filed None filed -- Dry hole 19
 Application for plugging approved Received permit dated 4/14/69 19
 Plugging commenced 4/10/69 19
 Plugging completed 4/10/69 19
 Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production ---- 19---
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, permission obtained from Mr. Eves before permit received.

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves notified of proposed plugging.
 Producing formation None Depth to top Bottom Total Depth of Well 5375 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
None	---	---	---	8 5/8	1722	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole full of mud pumped through drill pipe. Cement plugs set at:

1700' - 1600' with 35 sx.
 45' - G.L. with 15 sx.

RECEIVED
 STATE CORPORATION COMMISSION
 APR 28 1969
 CONSERVATION DIVISION
 Wichita, Kansas

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 1 1969
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services
 Address Liberal, Kansas

STATE OF Texas COUNTY OF Wichita, ss.
Jon H. Bear (employee of owner) or XXXXXXXXXXXX (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature] Jon H. Bear
Burk Royalty Co., 800 Oil & Gas Bldg., Wichita
 (Address) Falls, Texas

SUBSCRIBED AND SWORN TO before me this 25th day of April, 1969
[Signature] Averyl Uselton
 Notary Public.

My commission expires 6-1-69

BURK ROYALTY COMPANY

RECEIVED
STATE CORPORATION COMMISSION

C SW SW
Sec. 24-27-41W

LOWE NO. 1 WELL
Stanton County, Kansas

APR 30 1969
CONSERVATION DIVISION
Wichita, Kansas

COMMENCED OPERATIONS: 3-27-69
COMPLETED OPERATIONS: 4-10-69

DRILLERS LOG

3-27-69	0 - 210	Sand & RedBed.
3-28-69	210 - 1500	Sand, Red Bed & Gypsum.
3-29-69	1500 - 1722	Red Bed, Gypsum & Anhydrite.
3-30-69	1722 - 2570	Red Bed, Anhydrite & Shale.
3-31-69	2570 - 3121	Lime & Shale.
4-1-69	3121 - 3287	Lime & Shale.
4-2-69	3287 - 3722	Lime & Shale.
4-3-69	3722 - 4128	Lime & Shale.
4-4-69	4128 - 4522	Lime & Shale.
4-5-69	4522 - 4805	Lime & Shale.
4-6-69	4805 - 5122	Lime, Shale, Sand & Morrow Sand.
4-7-69	5122 - 5314	Shale & Lime.
4-8-69	5314 - 5350	Lime.
4-9-69	5350 - 5375	Lime & Shale.

Casing Record

3-29-69 Ran 59 Jts. of 8 5/8", 28# Used Casing.
Set at 1722 K.B. Cemented with 850 sacks pozmix
w/4% added Gel. and 2% c.c. and 150 sacks common
w/3% c.c.

4-10-69 Plugged hole with:
35 sacks @ 1700' to 1600'
15 sacks @ 45' to G.L.