

TATE OF KANSAS  
TATE CORPORATION COMMISSION  
00 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-081-10093-0000

API NUMBER Completed 5-16-60

LEASE NAME Pleasant Praire Unit

WELL NUMBER 56

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 6 TWP. 27s RGE. 34 (E) or (W)

COUNTY Haskell

Date Well Completed 5-16-60

Plugging Commenced 8-31-93

Plugging Completed 9-1-93

LEASE OPERATOR Helmerich & Payne, Inc.

ADDRESS P.O. Box 558 Garden City, KS 67846

PHONE# (316) 276-3693 OPERATORS LICENSE NO. 5293

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-30-93 (date)

by Dodge City - Glen Barlow (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation Mississippi Depth to Top 5047 Bottom 5124 T.D. 5185

Show depth and thickness of all water, oil and gas formations.

9-17-93

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippi	Oil	5047	5124	8-5/8"	800	0
Council Grove	Gas	2956	2820	5 1/2"	5180	0
Hugoton	Gas	2820	2541			

RECEIVED  
STATE CONSERVATION COMMISSION  
SEP 17 1993  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section.  
8-31-93 Move in to permanently abandon well. Set CIBP at 4930'. Dump bail 4 sks cmt on top of plug. Place cmt plug from 2970' to 2870' across DV tool at 2920' with 3 drop bailer runs for total of 12 sks cmt. Perforate below base of surface casing at 900' w/ 4 holes. Pumped 175 sks 65/35 Poz w/ 6% gel at 13.6 PPG with yield of 1.52 ft<sup>3</sup>/sk (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Dowell - Schlumberger License No. \_\_\_\_\_

Address Ulysses, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: \_\_\_\_\_

STATE OF Kansas COUNTY OF Haskell, ss.

Arthur R. Childers (Employee of Operator) or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Arthur R. Childers

(Address) P.O. Box 558 Garden City, KS

SUBSCRIBED AND SWORN TO before me this 16th day of September, 19 93

Judith Rehmeyer  
Notary Public

My Commission Expires: August 15, 1996

at rate of 3 BPM at 150 psi decreasing to no pressure. Good circulation for first 100 sks then no returns for remainder of job.

9-01-93 Pump into 8-5/8"X5½" annulus at 90 psi and 3.5 BPM at 130 psi. Pump 100 sks 65/35 Poz w/ 6% gel at 13.6 PPG with yield of 1.52 ft<sup>3</sup>/sk at 4 BPM at 100 psi increasing to 390 psi. Pump down 5½" casing pressured to 520 psi with no beed off.

9-02-93 Attempt to pump into 8-5/8"X5½" annulus. Pressured up and held 300#. Cut off casing 4 feet below surface. Weld on cap w/ identification and weep hole. Backfill hole around casing and recontour location. Plugging complete 9-3-93.

#### PLUG DETAIL

<u>PLUG</u>	<u>CONTENTS</u>	<u>PURPOSE</u>	<u>DEPTH</u>
1	CIBP and 4 sks cmt	Isolate production perforations	4930'-4895'
2	12 sks cmt	Isolate DV tool	2970'-2870'
3	275 sks cmt	Protect fresh water	900'-surface

Roland Leaton of BLM Elkhart, Kansas office witnessed plugging.  
Glen Barlow of Kansas Corporation Commission witnessd for KCC.

