

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Haskell County, Sec 24 Twp 27 Rge. 32 ~~(E)~~ (W)

Location as "NE/CNW/SW" or footage from lines 100' N & 100' W of Gen. Sec.

Lease Owner Cities Service Gas Development Co.

Lease Name Miller "T" Well No. 1

Office Address Bartlesville, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Show Gas, unable to shut off

Date well completed 4-6-55 water

Application for plugging filed 6-14-55 19

Application for plugging approved 6-15-55 19

Plugging commenced 11-4-55 19

Plugging completed 11-9-55 19

Reason for abandonment of well or producing formation Unable to shut off water

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 8, Pratt, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2790 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Hugoton	Water	2670	2748	8-5/8"	760	None
	Show Gas			5 1/2"	2789	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ran 2" tubing set Baker retrievable retainer at 2528', squeezed all perforations with 270 sacks cement to 3600#.

Fill hole with heavy rotary mud from 2528 to 775'; 5 sacks cement to 737'; heavy rotary mud to 34'; 4 1/2 sacks of cement to surface, 3 sacks cement between 5 1/2 & 8-5/8"; The casing was cut off 4' below surface and a steel cap was welded on the casing.

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1955
CONSERVATION DIVISION
Wichita, Kansas

11-15-55

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Oil Well Cem. Co. (no casing pulled)

Address Duncan, Oklahoma

STATE OF KANSAS, COUNTY OF SEWARD, ss.

H. V. Anderson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) H. V. Anderson

Box 70, Liberal, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of November, 19 55

My commission expires 5-23-1957

J. T. Mabrey J. T. Mabrey
Notary Public.

PLUGGING
FILE SEC. 24 T. 27 R. 32 W
BOOK PAGE 226 LINE 41