

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-081-00004-0000

API NUMBER Completed 3-18-56

LEASE NAME Pleasant Praire Unit

WELL NUMBER 54

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

3630 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 4 TWP. 27S RGE. 34 (E) or (W)

COUNTY Haskell

Date Well Completed 3-18-56

Plugging Commenced 8-30-93

Plugging Completed 8-31-93

LEASE OPERATOR Helmerich & Payne, Inc.

ADDRESS P.O. Box 558 Garden City, KS 67846

PHONE#(316) 276-3693 OPERATORS LICENSE NO. 5293

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-30-93 (date)

by Dodge City - Glenn Barlow (KCC District Agent's Name)

Is ACO-1 filed? no If not, is well log attached? yes

Producing Formation Mississippi "B" & "C" Depth to Top 5095 Bottom 5167 T.D. 5169

Show depth and thickness of all water, oil and gas formations.

9-17-93

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Mississippi	Oil	5095	5167	10-3/4"	777	0
Hugoton	Gas	2538	2742	5 1/2"	5169	0
Council Grove	Gas	2742	2906			

RECEIVED
STATE CORPORATION COMMISSION
SEP 17 1993

Describe in detail the manner in which the well was plugged, indicating where cement mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section.
8-30-93 Move in to permanently abandon well. Set CIBP at 5050'. Dump ball 4 sks cmt (35 ft) on top CIBP. Perforate base of Council Grove at 2960' w/ 4 holes. Squeeze w/ 140 sks 65/35 Poz w/ 6% gel at 13.6 PPG with yield of 1.52 ft³/sk. Drop wiper plug after cmt and displace w/ 9 #/gal mud to 2350' at 5 BPM with pressure increasing from (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Dowell - Schlumberger License No. _____

Address Ulysses, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Helmerich & Payne, Inc.

STATE OF Kansas COUNTY OF Haskell, ss.

Arthur R. Childers (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed is the same are true and correct, so help me God.

(Signature) Arthur R. Childers

(Address) P.O. Box 558 Garden City, KS

SUBSCRIBED AND SWORN TO before me this 14th day of September, 1993

Judith R. Reimer
Notary Public

My Commission Expires: August 15th, 1993

120 to 1220 psi. Attempt to go in hole with perforating gun to perforate base of surface casing could not due to thick mud.

8-31-93 RIH w/ perforating gun working down very slowly to 866'. Perforate 4 holes at 866' below the surface casing. Circulate 225 sks 65/35 Poz w/ 6% gel mixed at 13.6 PPG with yield of 1.52 ft³/sk at 2 BPM at pressure of 290 psi.

9-1-93 Cut off 5½" and 10-3/4" casing 4 feet below ground level. Weld on cap with identification and weep hole. Fill hole around casing and recontour location. Plugging complete 9-1-93.

PLUG DETAIL

<u>PLUG</u>	<u>CONTENTS</u>	<u>PURPOSE</u>	<u>DEPTH</u>
1	CIBP and 4 sks cmt	Isolate production perforaters	5050-5015'
2	140 sks cmt	Isolate Hugoton and Council Grove	2960-2350'
3	225 sks cmt	Protect fresh water	866-surface

Roland Leaton of BLM office in Elkhart, Kansas witnessed plugging. Glen Barlow witnessed plugging for Kansas Corporation Commission.

