

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-081-10092-0000  
API NUMBER Completed 1-26-62

LEASE NAME Pleasant Praire Unit

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 55

4620 Ft. from S Section Line

720 Ft. from E Section Line

SEC. 4 TWP. 27S RGE. 34 (E) or (W)

COUNTY Haskell

Date Well Completed 1-26-62

Plugging Commenced 8-30-93

Plugging Completed 8-31-93

LEASE OPERATOR Helmerich & Payne, Inc.

ADDRESS P.O. Box 558 Garden City, KS 67846

PHONE#(316) 276-3693 OPERATORS LICENSE NO. 5293

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-30-93 (date)

by Dodge City Glen Barlow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? yes

Producing Formation Miss B&C & St. Gen Depth to Top 5060 Bottom 5126 T.D. 5189

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED  
STATE CORPORATION COMMISSION

SEP 17 1993

CONSERVATION DIVISION  
Wichita, Kansas

Formation	Content	From	To	Size	Put in	Pulled out
Mississippi St. Gen	Oil	5060	5126	8-5/8"	997	0
Council Grove	Gas	2725	2954	5 1/2"	5184	0
Hugoton	Gas	2570	2725			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section.  
8-30-93 Rig up to permanently abandon well. Set cast iron bridge plug at 4970'. Dump bail 4 sks cmt (35 ft) on top of CIBP. Perforate base of Council Grove at 2954' w/ 4 holes. Squeeze w/ 140 sks 65/35 Poz w/ 6% gel at 136 PPG with yield of 1.52 ft<sup>3</sup>/sk. Drop wiper plug after cmt and displace to 2350' w/ 9 #/gal mud at 5 BPM with pressure (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Dowell - Schlumberger License No. \_\_\_\_\_

Address Ulysses, Ks

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Helmerich & Payne, Inc.

STATE OF Kansas COUNTY OF Haskell, ss.

Arthur R. Childers (Employee of Operator) or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed & the same are true and correct, so help me God.

(Signature) Arthur R. Childers

(Address) P.O. Box 558, Garden City, KS

SUBSCRIBED AND SWORN TO before me this 14th day of September, 1993

Judith R. Reimer  
Notary Public

My Commission Expires: August 15th 1996

increasing from 30 psi to 660 psi.

- 8-31-93 Attempt to go in hole w/ perforating gun to perforate below surface casing could not get below 50 feet. MIRU workover unit. TIH w/ 2-3/8" tbg to 1134' reverse circulating out thick mud. TOOH w/ tbg. Perforate 4 holes at 1096'. Circulate 212 sks 65/35 Poz w/ 6% gel at 136PPG yield 1.52 ft<sup>3</sup>/sk to surface at 3 BPM at 130 psi increasing to 630 psi.
- 9-01-93 Cut off 5½" and 8-5/8" casing 4 feet below ground level. Weld on cap with identification and weep hole. Backfill around casing and recontour location. Plugging complete 9-1-93.

**PLUG DETAIL**

<u>PLUG</u>	<u>CONTENTS</u>	<u>PURPOSE</u>	<u>DEPTH</u>
1	CIBP and 4 sks cmt	Isolate production perforations	4970-4935'
2	140 sks cmt	Isolate Hugoton and Council Grove	2954-2350'
3	212 sks cmt	Protect fresh water	1096-surface

Roland Leaton of BLM office in Elkhart, KS witnessed plugging. Glen Barlow witnessed plugging for Kansas Corporation Commission.

