

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Haskell Co. County. Sec. 11 Twp. 27S Rge. 31W (W)

Location as "NE/CNW/SW" or footage from lines C NE/4 of SW/4

Lease Owner J.M. Huber Corp.

Lease Name Ardery Well No. 1

Office Address Box 978, Liberal, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 2-2-56 19

Application for plugging filed 2-3-56 19

Application for plugging approved 2-3-56 19

Plugging commenced 2-3-56 19

Plugging completed 2-3-56 19

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M.A. Rives

Producing formation Depth to top Bottom Total Depth of Well 5249' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1680'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with mud to 600'. Set Halliburton plug at 600' and cemented with 35 sacks cement thru drill pipe. Filled with mud to 35'. Set Halliburton plug with 15 sacks cement to surface.

RECEIVED
STATE CORPORATION COMMISSION
FEB 8 1956
CONSERVATION DIVISION
Wichita, Kansas

2-8-56

Name of Plugging Contractor Moran Bros, Inc.
Address Oil & Gas Building, Wichita Falls, Texas

STATE OF KANSAS, COUNTY OF SEWARD, ss. W. W. Henson (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. W. Henson
Box 978, Liberal, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 7 day of February, 19 56

My commission expires 7-27-57

J. K. Key Notary Public.

PLUGGING
FILED FEB 11 1956
PAGE 27 LINE 13

DRILLER'S LOG

J. M. Huber Corporation

Artery No. 1

C NE SW Sec. 11-27S-31W

Haskell County, Kansas

Formation	From	To
Sand, gravel & Clay	0	501
Clay, Red bed & shells	501	1446
Red bed & anhy	1446	2001
Shale, Anhy & sand	2001	2205
Anhy & shale	2205	2354
Anhy, salt & shale	2354	2739
Anhy & sand	2739	2818
Shale & anhy	2818	2855
Chalky lime	2855	2893
Lime	2893	3348
Lime & shale	3348	3688
Lime	3688	3746
Lime & shale	3746	3824
Lime	3824	4222
Lime & chert	4222	4270
Lime	4270	4940
Lime & shale	4940	4968
Lime & chert	4968	5002
Lime	5002	5248 TD - SLM

CERTIFIED TRUE & CORRECT

MORAN BROS., INC.

By:

[Signature]
T. E. Swift

WITNESS:

[Signature]
Daisy Spencer

RECEIVED
STATE CORPORATION COMMISSION

FEB 23 1956

CONSERVATION DIVISION
Wichita, Kan.

COPY

PLUGGING
WELL SEC. 11-27-31W
BOOK PAGE 37 LINE 13