


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

HASKELL County. Sec. 20 Twp. 27S Rge. 31W (E) (W)
Location as "NE/CNW/SW" or footage from lines C NW SE



Locate well correctly on above
Section Flat

Lease Owner Sierra Petroleum Co., Inc. & Goff Oil Company
Lease Name NIGHTENGATE Well No. 1
Office Address 1015 Wichita Plaza, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 18/ 20, 19 64
Application for plugging filed January 20, 19 64
Application for plugging approved January 20, 19 64
Plugging commenced January 21, 19 64
Plugging completed January 21, 19 64
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh E. Scott, Liberal, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5475 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Clay, Sand, Shale, Shells</u>						
<u>Redbed & Salt</u>	<u>Surface Casing</u>	<u>-0-</u>	<u>1638'</u>	<u>8-5/8"</u>	<u>1638'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED: Filled with mud from 5475' up to 700'. Spotted 35 sx. cement. Filled with mud up to 40'. Set bridge, 1/2 sk. hulls, Halliburton plug & 10 sx. cement to cellar zero.

Job completed 7 a.m. 1-21-64.

RECEIVED
STATE CORPORATION COMMISSION

JAN 27 1964
1-27-64
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sierra Petroleum Co., Inc.
Address 1015 Wichita Plaza Bldg., Wichita, Kansas

STATE OF KANSAS COUNTY OF RUSSELL, ss.
S. P. Hall, Superintendent (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) S. P. Hall S. P. Hall, Superintendent
Box 232, Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of January 19 64

My commission expires 10-17-67

Larry Ditz
Notary Public.

SIERRA PETROLEUM CO., INC. & GOFF OIL COMPANY - Operators

NIGHTENGALE #1
C NW SE
Sec. 20-27S-31W
Haskell County, Kansas

T. D.: 5475'

Commenced: 12-19-63
Completed: 1-20-64

Casing:

8-5/8" Set at 1638'

Cement:

with 800 sx. Pozmix

FORMATION

DEPTH

Clay & Sand	69
Sand & Shells	623
Shale, Shells & Redbed	880
Redbed & Shale	1105
Redbed & Shells	1368
Sand	1530
Salt	1579
Shale Chalk	1625
Redbed & Shale	1649
Shale & Shells	2685
Lime & Shale	3074
Lime	3485
Lime w/ Chalk	3604
Lime	3937
Lime w/ Chalk Streaks	4047
Lime	5475 T.D.

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1964
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

S. P. Hall
Superintendent

Subscribed and sworn to before me this 23rd day of January,

1964.

Leroy Dietz
Notary Public

My commission expires: 10-17-67