

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-081-00099-0000
API NUMBER completed 7-26-55

LEASE NAME Black

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

3960 Ft. from S Section Line

3960 Ft. from E Section Line

LEASE OPERATOR Helmerich & Payne, Inc.

SEC. 19 TWP. 27 RGE. 31 (E) or (W)

ADDRESS P.O. Box 558, Garden City, KS 67846

COUNTY Haskell

PHONE# (316) 276-3693 OPERATORS LICENSE NO. 5293

Date Well Completed 7-26-55

Character of Well Gas

Plugging Commenced 1-10-95

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-11-95

The plugging proposal was approved on 12-28-94 (date)

by Steve Durant (KCC District Agent's Name)

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation Hugoton Chase Depth to Top 2664 Bottom 2694 T.D. 2715

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Dakota	Water	720	880	8-5/8"	508	0
Cheyenne	Water	910	1050	4 1/2"	2714	0
Hugoton Chase	Gas	2664	2715			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other p were used, state the character of same and depth placed, from feet to feet each
MIRU completion unit BTH w/ chemical cutting tool for 1 1/2" tubing. Chemical cut tubing at 2112'
TOOH w/ 1 1/2" tubing. TTH w/ 2-3/8" x 1/2" cement retainer on 2-3/8" tubing. Set retainer at 1202'
RU Halliburton. Sting into retainer. Establish injection rate down tubing 2 1/2 BPM at 50 psi.
Mix and pump 65 sacks 65/35 Poz "C" cement. Squeezed to 500 psi with 30 sacks 65/35 Poz "C" below
(If additional description is necessary, use BACK of this form.) (over)


Name of Plugging Contractor Halliburton License No. _____

Address Liberal, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Helmerich & Payne, Inc.

STATE OF Kansas COUNTY OF Finney, ss.

Ken Jehik (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fa
statements, and matters herein contained and the log of the above-described well as filed
the same are true and correct, so help me God.



(Signature) Ken Jehik
Address P.O. Box 558, Garden City, KS
13th day of January, 1995
Judy Richmeier
Notary Public

My Commission Expires: August 13, 1996

retainer. Reverse out excess cement. TOOH w/ 2-3/8" tubing. RIH and perforate 4 holes at 1050'. RU Halliburton. Mix and pump 250 sacks 65/35 Poz "C" w/ 6% gel. Circulated cement back to surface on 8-5/8" x 4 1/2" annulus and left 4 1/2" casing full of cement. RO Halliburton. RDCU. Cut off 8-5/8" and 4 1/2" casing 5' below ground level. Reclaim location.

*Witnessed by Richard Lacey
KSCC - Dodge City*

