


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Sedgwick County. Sec. 35 Twp. 26S Rge. 1 (E) W (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE $\frac{1}{4}$  of NW $\frac{1}{4}$  of NW $\frac{1}{4}$   
Lease Owner Drillers Production Co.  
Lease Name Petria Well No. 1  
Office Address 212 N. Market St., Wichita 2, Kansas.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5/7-51 19  
Application for plugging filed 5/7-51 19  
Application for plugging approved 5/7-51 19  
Plugging commenced 5/7-51 19  
Plugging completed 5/7-51 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Lilly  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3658 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	222 ft.	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled the hole with heavy mud up into the Surface Pipe and set the plug and 15 sacks of cement. Filled up Surface Pipe with mud and cemented top with 5 sacks of cement.

6-16-51

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 16 1951  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Drillers Production Co.  
Address 212 N. Market St.,  
Wichita 2, Kansas.

STATE OF \_\_\_\_\_, COUNTY OF \_\_\_\_\_, ss.

\_\_\_\_\_, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Springer & Harper  
By L. L. Harper  
L. L. Harper (Address)

SUBSCRIBED AND SWORN TO before me this 21 day of May, 1951

Betha L. Wilson

Notary Public.

My commission expires August 13, 1951

23-5081-8 8-50-10M  
**PLUGGING**  
FILE SEC 35 T 26 R 1W  
FOOT PAGE 80 LINE 18

15-173-00045-0000

KANSAS WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY  
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY THE DRILLERS PRODUCTION CO.

SEC. 35 T. 26 R. 1W  
LOC. SE NW NW

FARM Petrie

NO. 1

TOTAL DEPTH 3558

COMM. 4-21-51


COMP. 5-7-51

SHOT OR TREATED

CONTRACTOR Springer & Harper

ISSUED 6-16-51

COUNTY Sedgwick



CASING

8 5/8" 222' cem. w/250 sx

ELEVATION 1336 R.B.

PRODUCTION Dry

FIGURES INDICATE BOTTOM OF FORMATIONS

sand	110	DST: 3098-3105, open 45 min.
shale & shells	185	rec. 15' mud.
lime	222	DST: 3445-48, open 15 min.
anhydrite	440	rec. 100' gassy oil
shale & shells	545	120' gassy OCM
shale & lime	705	600' sulfhur wtr
lime & shale	740	DST 3458-74, open 45 mins.
red bed	752	rec. 50' mud.
lime & shale	1105	
sand	1160	
shale & shells	1300	
shale & lime	1505	
shale	1680	
lime	1730	
lime & shale	1895	
lime	1960	
sand	1990	
lime	2220	
shale	2235	
lime	2358	
shale	2442	
lime	2510	
lime & shale	2610	
lime	2795	
shale	2842	
lime	3015	
lime & shale	3096	
chat	3105	
chert	3170	
lime	3385	
shale	3447	
lime	3474	
sand	3494	
lime	3530	
sand & shale	3542	
arb. lime	3558	
Total Depth		

Tops:

Brown Lime	2292
Lansing	2378
Kansas City	2609
Miss.	3096
Viola	3447
Simpson	3453
Arbuckle	3542

DST: 2661-71, open 30 min.,  
rec. 15' mud.  
DST: 2705-25, open 30 min.  
rec. 380' gas cut muddy salt  
wtr.

**PLUGGING**  
FILE SEC 35 T 26 R 1W  
BOOK PAGE 80 LINE 12

RECEIVED  
STATE CORPORATIONS COMMISSIONER  
JUN 16 1951  
CONSULTING DIVISION  
WICHITA, KANSAS