

15-173-00052-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Sedgwick

County. Sec. 35 Twp. 26 Rge. ~~25~~ 1 (W)

Location as "NE/CNW/SW" or footage from lines. NE SW NW

Lease Owner Drillers Production Company, Inc.

Lease Name Petrie Well No. 2

Office Address Insurance Bldg. - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed October 14 19 51

Application for plugging filed April 13 19 53

Application for plugging approved April 14 19 53

Plugging commenced April 30 19 53

Plugging completed May 4 19 53

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production March 19 53

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Viola Depth to top 3446 Bottom 3454 Total Depth of Well 3466 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	FULLED OUT
Lansing		2325		5-1/2"	3465'	2233'
K.C.		2605		8-5/8"	219'	None
Miss.		3098				
Viola		3446				
Smp.		3454				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded hole from 3448' to 3438' and ran 6 sacks of cement. Checked mud at 220', set 10' rock bridge and ran 15 sacks of cement. Mudded hole to 30', set rock bridge and ran 5 sacks of cement. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company

Address Chase, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.

G. R. Bickford, Jr. (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *G. R. Bickford, Jr.*

Insurance Bldg., 212 N. Market, Wichita, Kans. (Address)

SUBSCRIBED AND SWORN TO before me this 27 day of May, 1953

Betha L. Wilson Notary Public.

My commission expires August 13, 1955

24-2675-5 2-52-20M

PLUGGING
FILE SEC-35-T-26-R-1W
BOOK PAGE 92 LINE 44

CONSERVATION DIVISION
Wichita, Kansas
MAY 27 1953
5-28-53

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas


15-173-00052-0000

Company- DRILLERS PRODUCTION COMPANY
Farm- Petrie No. 2

SEC. 35 T. 26 R. 1W
NE SW NW

Total Depth. 3466
Comm. 7-31-51 Comp. 10-14-51
Shot or Treated.
Contractor. Springer & Harper
Issued. 1-12-52

County Sedgwick
KANSAS



CASING:
8 5/8" 218.95' cem w/250 sx
5 1/2" 3465' cem w/150 sx

Elevation. 1335 BB.

Production. Pump 60 bbls / 900
BWPD

Figures Indicate Bottom of Formations.

sand, shale	95
lime, shale	150
anhydrite	225
anhydrite, shale	305
shale, lime	925
lime	1000
lime, shale	1265
shale, shells	1565
lime	1600
shale	1650
shale, lime	1897
lime	2160
lime, shale	2330
lime	2380
shale	2440
lime, shale	2599
shale	2610
lime	2784
lime, shale	3093
shale	3098
lime	3160
lime, chert	3195
lime	3305
lime, shale	3440
sand	3466
Total Depth	

Tops:
Lansing 2329
Kansas City 2608
Mississippi 3100
Kinderhook 3338
Viola 3444
Simpson 3452

Perf. 1/S 3447, Swb 13 BO
/ 88BW/6 hrs.

Perf. 5/S 3445-46 wh & sl
show oil

Perf 27/S 3446-55 squeeze perfs
CO 3453 1/2.

Perf. 11/S 3450-52 1 BWPH
Perf 3/S 3452-53
Perf 4/S 3447
PB 3448
250 gal acid
pump test 60 BO / 900 BWPD

DST: 2723-27, op. 45 min.,
rec. 10' oil & wtr cut
mud, 120' muddy salt wtr.
DST: 3451-55, op. 15 min., Rec
150' oil, 75' hly oil &
cut mud, 1275' wtr.
DST: 3455-60, op. 20 min., rec.
240' wtr, sl gas cut.

RECEIVED
STATE COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS

RECEIVED
STATE CORPORATION COMMISSION
MAY 11 1953
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 35 T 26 R 1W
BOOK PAGE 92 LINE 44