

15-173-01470-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Sedgwick County. Sec. 26 Twp. 26 Rge. 1 (E) 1 (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW

Lease Owner E. H. Adair

Lease Name Woodman Well No. 1

Office Address 407 W-K-H Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Nov. 11 19 52

Application for plugging filed Dec. 9 19 52

Application for plugging approved Dec. 9 19 52

Plugging commenced Dec. 10 19 52

Plugging completed Dec. 10 19 52

Reason for abandonment of well or producing formation Barren

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well D. C. Lilley

Producing formation          Depth to top          Bottom          Total Depth of Well 3466 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5 1/2"	3456 1/2	2725

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet for each plug set.

Filled with mud to 117', put in rock bridge, dumped 15 sx cement, filled with mud to 20' of surface, dumped 5 sx cement, filled to surface.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 2 - 1953

1-2-53

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor E. H. Adair Oil Company  
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. Russell I. Baker (employee of owner) of owner of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Russell I. Baker

Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of December, 1952

My commission expires September 15, 1953

23-8390-s 6-51-20M

PLUGGING  
FILE SEC 26 T 26 R 12  
BOOK PAGE 64 LINE 16

Notary Public.

15-173-01470-0000

Company: E. H. Adair Oil Company  
& WM. Graham Oil Co.

Sec. 26 R. 26 R. 1W  
Loc. SW SW SW

Lease: Woodman No. 2

County: Sedgwick

Total depth: 3457 w/rotary  
Comm. 10-30-52  
Comp. 11-11-52 w/rotary  
Casing: 8 5/8 at 117' w/90 sax cement.  
5 1/2 at 3456 1/2 w/50 sax cement.


Elev. 1341 KB  
1336 Ground  
Production:

Figures indicate bottom of ftns.

Sand	80	Geological Tops:	
Shale & Shells	117	Topeka Lime	1885 -544
Shale	520	Heebner Shale	2079 -738
Lime	540	Douglas Shale	2116 -775
Shale	601	Brown Lime	2300 -959
Shale & Shells	786	Lansing Lime	2341 -1000
Shale	1600	Kansas City Lime	2609 -1268
Lime	1605	Base K.C.	2780 -1439
Lime & Shale	1885	Miss. Chert	3103 -1762
Lime	2011	Base Miss.	3354 -2013
Lime & Shale	2154	Viola Dolomite	3455 -2114
Shale	2235		
Shale & Shells	2300		
Brown Lime	2307		
Shale	2341		
Lansing Lime	2372		
Shale & Shells	2405		
Shale	2609		
K.C. Lime	2784		
Shale	2920		
Shale & Shells	3027		
Shale & Shells	3071		
Shale	3101		
Chat	3169		
Chat & Lime	3216		
Lime	3308		
Shale & Lime	3340		
Lime	3354		
Shale	3455		
Viola Dolomite	3457		
Rotary T.D.	3457		

Certified Correct

*Russell Baker*



DEPARTMENT OF MINES